

STORMWATER MANAGEMENT ORDINANCE

ORDINANCE NO. 2023-117

MUNICIPALITY OF:
HAMILTON TOWNSHIP
ADAMS COUNTY, PENNSYLVANIA

Adopted at a Public Meeting Held on

DECEMBER 4, 2023

Article I – General Provisions

Section 101 Short Title
Section 102 Statement of Findings
Section 103 Purpose
Section 104 Statutory Authority
Section 105 Applicability
Section 106 Repealer
Section 107 Severability
Section 108 Compatibility with Other Requirements
Section 109 Erroneous Permit
Section 110 Waivers
Section 111 Amendment

Article II – Definitions

Section 201 Definitions

Article III – Stormwater Management Standards

Section 301 General Requirements
Section 302 Exemptions
Section 303 Volume Controls
Section 304 Rate Controls
Section 305 Riparian Buffers
Section 306 Design Criteria
Section 307 Regulations Governing SWM Facilities
Section 308 Calculation Methodology
Section 309 Carbonate Geology
Section 310 Erosion and Sedimentation Control Requirements

Article IV – Stormwater Management Site Plan Requirements

Section 401 Plan Requirements
Section 402 Plan Submission
Section 403 Plan Review
Section 404 Modification of Plans
Section 405 Resubmission of Disapproved SWM Site Plans
Section 406 Authorization to Construct and Term of Validity

Section 911	Right-of-Entry
Section 912	Inspection
Section 913	Notifications
Section 914	Enforcement
Section 915	Suspension and Revocation
Section 916	Penalties
Section 917	Appeals

Article X – References

Section 1001	References
--------------------	------------

Tables

Table 1 – Runoff Curve Numbers
Table 2 – Rational Runoff Coefficients
Table 3 – Roughness Coefficients

Appendix A – Operation and Maintenance Agreement

Appendix B – Infiltration Testing

Appendix C – Small Project Approach

Section 407As-Built Plans, Completion Certificate, and Final Inspection
 Section 408Financial Security

Article V – Construction Inspections

Section 501Schedule of Inspections

Article VI – Operation and Maintenance

Section 601Responsibilities of Developers and Landowners
 Section 602Operation and Maintenance Agreements

Article VII – Fees and Expenses

Section 701 General

Article VIII – Prohibitions

Section 801Ultimate Responsibility
 Section 802Prohibited Discharges and Connections
 Section 803 Roof Drains and Sump Pumps
 Section 804 Alterations of SWM BMPs
 Section 805 Suspension of MS4 Access
 Section 806 Industrial or Construction Activity Discharges
 Section 807 Monitoring of Discharges
 Section 808 Requirements to Prevent, Control, and Reduce Stormwater Pollutants by the Use of BMPs
 Section 809 Watercourse Protection
 Section 810Notification of Spills

Article IX – Enforcement and Penalties

Section 901Enforcement
 Section 902 Appeals of Notice of Violation
 Section 903 Enforcement Measures after Appeal
 Section 904 Cost of Abatement of Violation
 Section 905 Injunctive Relief
 Section 906Compensatory Action
 Section 907 Violations Deemed as Public Nuisance
 Section 908Criminal Prosecution and Penalties
 Section 909 Attorney Fees and Costs
 Section 910 Remedies Not Exclusive

ARTICLE I – GENERAL PROVISIONS

Section 101. Short Title

This Ordinance shall be known and may be cited as the “Hamilton Township Stormwater Management Ordinance.”

Section 102. Statement of Findings

The governing body of the Municipality finds that:

- A. Inadequate management of accelerated runoff of stormwater resulting from development throughout a watershed increases runoff volumes, flows and velocities, contributes to erosion and sedimentation, overtaxes the carrying capacity of streams and storm sewers, greatly increases the cost of public facilities to carry and control stormwater, undermines floodplain management and flood control efforts in downstream communities, reduces groundwater recharge, threatens public health and safety, and increases nonpoint source pollution of water resources.
- B. A comprehensive program of stormwater management (SWM), including reasonable regulation of development and activities causing accelerated runoff, is fundamental to the public health, safety, and welfare and the protection of the people of the Commonwealth, their resources, and the environment.
- C. Stormwater is an important water resource that provides groundwater recharge for water supplies and supports the base flow of streams.
- D. The use of green infrastructure and low impact development (LID) is intended to address the root cause of water quality impairment by using systems and practices which use or mimic natural processes to 1) infiltrate and recharge, 2) evapotranspire, and 3) harvest and use precipitation near where it falls to earth. Green infrastructure practices and LID contribute to the restoration or maintenance of pre-development hydrology.
- E. Federal and state regulations require certain municipalities to implement a program of stormwater controls called a Municipal Separate Storm Sewer System (MS4) Program. These municipalities are required to obtain a permit for stormwater discharges from their separate storm sewer systems under the National Pollutant Discharge Elimination System (NPDES) program.

Section 103. Purpose

The purpose of this Ordinance is to promote health, safety, and welfare within the Municipality and its watershed by minimizing the harms and maximizing the benefits described in Section 102 of this Ordinance, through provisions designed to:

- A. Meet legal water quality requirements under state law, including regulations at 25 Pa. Code 93 to protect, maintain, reclaim, and restore the existing and designated uses of the waters of this Commonwealth.
- B. Preserve natural drainage systems.
- C. Manage stormwater runoff close to the source, reduce runoff volumes, and mimic pre-development hydrology.
- D. Provide procedures and performance standards for stormwater planning and management.
- E. Maintain groundwater recharge to prevent degradation of surface and groundwater quality and to otherwise protect water resources.

- F. Prevent scour and erosion of stream banks and streambeds.
- G. Provide proper operation and maintenance of all stormwater best management practices (BMPs) implemented within the Municipality.
- H. Provide standards to meet and enforce NPDES permit requirements.
- I. Create a platform to advocate and grow the use of low-impact development procedures and green infrastructure.

Section 104. Statutory Authority

The Municipality is empowered to regulate land use activities that affect runoff by the authority of the Act of July 31, 1968, P.L. 805, No. 247, The Pennsylvania Municipalities Planning Code, as amended, and/or the Act of October 4, 1978, P.L. 864 (Act 167), 32 P.S. Section 680.1, et seq., as amended, The Stormwater Management Act.

Section 105. Applicability

All Regulated Activities and all activities that may affect stormwater runoff, including land development and earth disturbance activity, are subject to regulation by this Ordinance.

Section 106. Repealer

Any other ordinance provision(s) or regulation of the Municipality inconsistent with any of the provisions of this Ordinance is hereby repealed to the extent of the inconsistency only.

Section 107. Severability

If a court of competent jurisdiction declares any section or provision of this Ordinance invalid, such a decision shall not affect the validity of any remaining provisions of this Ordinance.

Section 108. Compatibility with Other Requirements

Approvals issued and actions taken under this Ordinance do not relieve the Applicant of the responsibility to secure required permits or approvals for activities regulated by any other code, law, regulation, or ordinance.

Section 109. Erroneous Permit

Any permit or authorization issued or approved based on false, misleading, or erroneous information provided by an Applicant is void without the necessity of any proceedings for revocation. Any work is undertaken or uses established pursuant to such permit or other authorization is unlawful. No action may be taken by a board, agency, or employee of the Municipality purporting to validate such a violation.

Section 110. Waivers

- A. If the Municipality determines that any requirement under this Ordinance cannot be achieved for a particular Regulated Activity, the Municipality may, after evaluating alternatives, approve measures other than those in this Ordinance, subject to Section 110, paragraphs B and C.

- B. Waivers or modifications of the requirements of this Ordinance may be approved by the Municipality if enforcement will exact undue hardship because of peculiar conditions pertaining to the land in question, provided that the modifications will not be contrary to the public interest and that the purpose of the Ordinance is preserved. Cost or financial burden shall not be considered a hardship. Modification may be considered if an alternative standard or approach will provide equal or better achievement of the purpose of the Ordinance. A request for modifications shall be in writing and accompany the Stormwater Management Site Plan submission. The request shall provide the facts on which the request is based, the provision(s) of the Ordinance involved, and the proposed modification.
- C. No waiver or modification of any regulated stormwater activity involving earth disturbance greater than or equal to one acre may be granted by the Municipality unless that action is approved in advance by the Department of Environmental Protection (DEP) or the delegated county conservation district.

Section 111. Amendment

- A. Amendments to the Appendices and Tables attached to this Ordinance may be made from time to time by Resolution of the approval body.

ARTICLE II – DEFINITIONS

Section 201. Definitions

For the purposes of this Ordinance, certain terms and words used herein shall be interpreted as follows:

- A. Words used in the present tense include the future tense; the singular number includes the plural, and the plural number includes the singular; words of masculine gender include feminine gender, and words of feminine gender include masculine gender.
- B. The word “includes” or “including” shall not limit the term to the specific example but is intended to extend its meaning to all other instances of like kind and character.
- C. The words “shall” and “must” are mandatory; the words “may” and “should” are permissive.
- D. Any term defined within 25 PA Code (Chapter 102) shall be the default definition.

These definitions do not necessarily reflect the definitions contained in pertinent regulations or statutes and are intended for this Ordinance only.

Agricultural Activity – Activities associated with agriculture such as agricultural cultivation, agricultural operation, and animal heavy use areas. This includes the work of producing crops, including tillage, land clearing, plowing, disking, harrowing, planting, harvesting crops, or pasturing and raising of livestock and installation of conservation measures. Construction of new buildings or impervious area is not considered an agricultural activity.

Applicant – A landowner, developer, or another person who has filed an application to the Municipality for approval to engage in any Regulated Activity at a project site in the Municipality.

Best Management Practice (BMP) – Activities, facilities, designs, measures, or procedures used to manage stormwater impacts from Regulated Activities, to meet state water quality requirements, to promote groundwater recharge, and to otherwise meet the purposes of this Ordinance. Stormwater BMPs are commonly grouped into one of two broad categories or measures: “structural” or “non-structural.” In this Ordinance, non-structural BMPs or measures refer to operational and/or behavior-related practices that attempt to minimize the contact of pollutants with stormwater runoff, whereas structural BMPs or measures are those that consist of a physical device or practice that is installed to capture and treat stormwater runoff. Structural BMPs include, but are not limited to, a wide variety of practices and devices, from large-scale retention ponds and constructed wetlands to small-scale underground treatment systems, infiltration facilities, filter strips, low impact design, bioretention, wet ponds, permeable paving, grassed swales, riparian or forested buffers, sand filters, detention basins, and manufactured devices. Structural stormwater BMPs are permanent appurtenances to the project site.

Carbonate Geology – See definition of Karst

CG-1 (Control Guideline – 1) – A standard method for design flood estimation in ungauged catchments that investigates set design storms characterized by a specific duration, temporal distribution, rainfall intensity, return frequency, and total depth of rainfall.

CG-2 (Control Guideline – 2) – A simplified method for design storm estimation that is focused on capturing and removing the first flush of stormwater runoff. This method is applicable to designing projects with a land disturbance of 0.5 acres or less.

Clean Water Act (CWA) – Means the Federal Water Pollution Control Act, as amended, 33 U.S.C.A. §§ 1251 - 1387.

Cleaning Agent – Any product, substance, or chemical other than water that is used to clean.

Conservation District – A conservation district, as defined in Section 3(c) of the Conservation District Law (3 P. S. § 851(c)) that has the authority under a delegation agreement executed with DEP to administer and enforce all or a portion of the regulations promulgated under 25 Pa. Code 102.

Design Storm – The magnitude and temporal distribution of precipitation from a storm event measured in probability of occurrence (e.g., a 5-year storm) and duration (e.g., 24 hours) used in the design and evaluation of stormwater management systems. Also, see Return Period.

Detention Volume – The volume of runoff that is captured and released into the waters of the Commonwealth at a controlled rate.

DEP – The Pennsylvania Department of Environmental Protection.

Development Site (Site) – See Project Site.

Disturbed Area – An unstabilized land area where an earth disturbance activity is occurring or has occurred.

Earth Disturbance Activity – A construction or other human activity which disturbs the surface of the land, including, but not limited to: clearing and grubbing; grading; excavations; embankments; road maintenance; building construction; and the moving, depositing, stockpiling, or storing of soil, rock, or earth materials.

Erosion – The natural process by which the surface of the land is worn away by water, wind, or chemical action.

Existing Condition – The initial condition of a project site prior to the proposed construction.

FEMA – Federal Emergency Management Agency.

Floodplain – Any land area susceptible to inundation by water from any natural source or delineated by applicable FEMA maps and studies as being a special flood hazard area. It also includes areas that comprise Group 13 Soils, as listed in Appendix A of the Pennsylvania DEP Technical Manual for Sewage Enforcement Officers (as amended or replaced from time to time by DEP).

Floodway – The channel of the watercourse and those portions of the adjoining floodplains that are reasonably required to carry and discharge the 100-year flood. Unless otherwise specified, the boundary of the floodway is as indicated on maps and flood insurance studies provided by FEMA. In an area where no FEMA maps or studies have defined the boundary of the 100-year floodway, it is assumed--absent evidence to the contrary--that the floodway extends from the stream to 50 feet from the top of the bank of the stream.

Forest Management/Timber Operations – Planning and activities necessary for the management of forestland. These include conducting a timber inventory, preparation of forest management plans, silvicultural treatment, cutting budgets, logging road design and construction, timber harvesting, site preparation, and reforestation.

Green Infrastructure – Systems and practices that use or mimic natural processes to infiltrate, evapotranspire, or reuse stormwater on the site where it is generated.

HEC-RAS (Hydrological Engineering Center – River Analysis System) – Is a hydraulic modeling program based on four types of analysis in rivers: Steady Flow, Unsteady Flow, Sediment Transport, and Water Quality Analysis. Models simulate the flow in natural riverbeds or artificial channels to determine water levels using various data inputs. HEC-RAS Analyses are primarily developed for flood studies and determining potential drainage impacts to waterways.

Hydrologic Soil Group (HSG) – Infiltration rates of soils vary widely and are affected by subsurface permeability as well as surface intake rates. Soils are classified into four HSGs (A, B, C, and D) according to their minimum infiltration rate, which is obtained for bare soil after prolonged wetting. The Natural Resources Conservation Service (NRCS) defines the four groups and provides a list of most of the soils in the United States and their group classification. The soils in the area of the development site may be identified from a soil survey report that can be obtained from local NRCS offices or conservation district offices. Soils become less pervious as the HSG varies from A to D (NRCS^{1,2}).

Illicit Connection – Any physical connection to a municipal separate storm sewer system that can convey illicit discharges into the system.

Illicit Discharge – Any discharge to a municipal separate storm sewer that is not composed entirely of stormwater, except non-stormwater discharges as described in the “Discharges Authorized by this General Permit” section of this General Permit. Examples of illicit discharges include dumping of motor vehicle fluids, household hazardous wastes, grass clippings, leaf litter, animal wastes, or unauthorized discharges of sewage, industrial waste, restaurant wastes, or any other non-stormwater waste into a municipal separate storm sewer system. Illicit discharges can be accidental or intentional.

Impaired Waters – Surface waters that fail to attain one or more of their designated uses under 25 Pa. Code Chapter 93 and as listed in Categories 4 and 5 of Pennsylvania’s Integrated Water Quality Monitoring and Assessment Report.

Impervious Surface (Impervious Area) – A surface that prevents the infiltration of water into the ground. Impervious surfaces (or areas) shall include, but not be limited to: roofs; additional indoor living spaces, patios, garages, storage sheds, and similar structures; and any new streets, driveway, access drives, parking areas, and sidewalks. Any areas designed to be covered by loose surfacing materials such as gravel, stone, and/or crushed stone and intended for storage of and/or travel by motorized or non-motorized vehicles or travel by pedestrians shall be considered impervious. Surfaces or areas designed, constructed, and maintained to permit infiltration as specified herein may be considered pervious. For the purposes of this Ordinance, a surface or area shall not be considered impervious if such surface or area does not diminish the capacity for infiltration of stormwater for storms up to, and including, a two (2)-year, 24-hour storm event.

Karst – A type of topography or landscape characterized by surface depressions, sinkholes, rock pinnacles/uneven bedrock surface, underground drainage, and caves. Karst is formed on carbonate rocks, such as limestone or dolomite.

Land Development (Development) – Inclusive of any or all of the following meanings: (i) the improvement of one lot or two or more contiguous lots, tracts, or parcels of land for any purpose involving (a) a group of two or more buildings or (b) the division or allocation of land or space between or among two or more existing or prospective occupants by means of, or for the purpose of streets, common areas, leaseholds, condominiums, building groups, or other features; (ii) any subdivision of land; (iii) development in accordance with Section 503(1.1) of the PA Municipalities Planning Code.

Low Impact Development (LID) – Site design approaches and small-scale stormwater management practices that promote the use of natural systems for infiltration, evapotranspiration, and reuse of rainwater. LID can be applied to new development, urban retrofits, and revitalization projects. LID utilizes design techniques that infiltrate, filter, evaporate, and store runoff close to its source. Rather than rely on large-scale conveyance and treatment systems, LID addresses stormwater through a variety of small, cost-effective landscape features located on-site.

Municipal Separate Storm Sewer – A conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains): (i) Owned or operated by a State, City, Town, Municipality, County, Parish, District, Association, or other public body (created by or pursuant to State law) having jurisdiction over disposal of sewage, industrial wastes, stormwater, or other wastes, including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or an Indian tribe or an authorized Indian tribal organization, or a designated and approved management agency under section 208 of the CWA that discharges to surface waters; (ii) Designed or used for collecting or conveying stormwater; (iii) Which is not a combined sewer; and (iv) Which is not part of a Publicly Owned Treatment Works (POTW) as defined at 40 CFR 122.2. (25 Pa. Code § 92a.32(a) and 40 CFR § 122.26(b)(8))

Municipal Separate Storm Sewer System (MS4) – All separate storm sewers that are defined as “large” or “medium” or “small” municipal separate storm sewer systems pursuant to 40 CFR §§ 122.26(b)(4), (b)(7), and (b)(16), respectively, or designated under 40 CFR § 122.26(a)(1)(v). (25 Pa. Code § 92a.32(a) and 40 CFR § 122.26(b)(18))

Municipality – Hamilton Township, Adams County, Pennsylvania

Non-Structural BMPs – Actions that involve management and source controls such as (1) policies and ordinances that provide requirements and standards to direct growth to identified areas, promote redevelopment, protect areas such as wetlands and riparian areas, maintain and/or increase open space, provide buffers along water bodies, minimize impervious surfaces, and minimize disturbance of soils and vegetation; (2) education programs for developers and the public about minimizing water quality impacts; (3) measures such as minimizing the percentage of impervious area after development, use of measures to minimize directly connected impervious areas, and source control measures such as good housekeeping, maintenance, and spill prevention; and other BMPs as referenced in the current version of the Pennsylvania Stormwater BMP Manual.

NRCS – Natural Resources Conservation Service, a subset of the United States Department of Agriculture.

Outfall – A point source as defined by 40 CFR § 122.2 at the point where a municipal separate storm sewer discharges to surface waters and does not include open conveyances connecting two municipal separate storm sewers, or pipes, tunnels, or other conveyances which connect segments of the same stream or other surface waters and are used to convey surface waters. (25 Pa. Code § 92a.32(a) and 40 CFR § 122.26(b)(9))

Owner or Operator – The owner or operator of any “facility” or “activity” subject to regulation under the NPDES program. (25 Pa. Code § 92a.3(b)(1) and 40 CFR § 122.2)

Permittee – The owner or operator of a regulated small MS4 authorized to discharge under the terms of this General Permit.

Point Source – A discernible, confined, and discrete conveyance, including, but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, Concentrated Aquatic Animal Production Facility (CAAP), Concentrated Animal Feeding Operation (CAFO), landfill leachate collection system, or vessel or other floating craft from which pollutants are or may be discharged. (25 Pa. Code § 92a.2)

Pollutant – any contaminant or other alteration of the physical, chemical, biological, or radiological integrity of surface water which causes or has the potential to cause pollution as defined in section 1 of the Pennsylvania Clean Streams Law, 35 P.S. § 691.1. (25 Pa. Code § 92a.2)

Peak Discharge – The maximum rate of stormwater runoff from a specific storm event.

Pervious Area – Any area not defined as impervious.

Project Site – The specific area of land where any Regulated Activities in the Municipality are planned, conducted, or maintained.

PSRM – The Penn State Runoff Model.

PULS Method – The Modified PULS routing method, also known as storage routing or level-pool routing, is based upon a finite difference approximation of the continuity equation, coupled with an empirical representation of the momentum equation (Chow, 1964; Henderson, 1966).

Qualified Professional – Any person licensed by the Pennsylvania Department of State or otherwise qualified by law to perform the work required by this Ordinance.

Regulated Activities – Any earth disturbance activities or any activities that involve the alteration or development of land in a manner that may affect stormwater runoff.

Regulated Earth Disturbance Activity – Activity involving earth disturbance subject to regulation under 25 Pa. Code 92, 25 Pa. Code 102, or the Clean Streams Law.

Retention Volume/Removed Runoff – The volume of runoff that is captured and not released directly into the surface waters of this Commonwealth during or after a storm event.

Return Period – The average interval, in years, within which a storm event of a given magnitude can be expected to occur one time. For example, the twenty-five (25)-year return period rainfall would be expected to occur on average once every twenty-five (25) years; or stated in another way, the probability of a twenty-five (25)-year storm occurring in any one year is 0.04 (i.e., a 4% chance).

Riparian Buffer – An area of trees and shrubs located adjacent to streams, lakes, ponds and wetlands.

Runoff – Any part of precipitation that flows over the land.

Structural BMPs – Stormwater storage and management practices including, but not limited to, wet ponds and extended detention outlet structures; filtration practices such as grassed swales, sand filters, and filter strips; infiltration practices such as infiltration basins and infiltration trenches; and other BMPs as referenced in the current version of the Pennsylvania Stormwater BMP Manual.

Surface Waters – Perennial and intermittent streams, rivers, lakes, reservoirs, ponds, wetlands, springs, natural seeps, and estuaries, excluding water at facilities approved for wastewater treatment such as wastewater treatment impoundments, cooling water ponds, and constructed wetlands used as part of a wastewater treatment process. (25 Pa. Code § 92a.2)

Sediment – Soils or other materials transported by surface water as a product of erosion.

SCS Curve Number Method – The SCS curve number method is simple, widely used, and an efficient method for determining the approximate amount of runoff from a rainfall event in a particular area. Although the method is designed for a single storm event, it can be scaled to find average annual runoff values. The curve number is based on the area's hydrologic soil group, land use, treatment, and hydrologic condition.

State Water Quality Requirements – The regulatory requirements to protect, maintain, reclaim, and restore water quality under Title 25 of the Pennsylvania Code and the Clean Streams Law.

Stormwater – Drainage runoff from the surface of the land resulting from precipitation or snow or ice melt.

Stormwater Management Facility – Any structure, natural or man-made, that, due to its condition, design, or construction, conveys, stores, or otherwise affects stormwater runoff. Typical stormwater management facilities include but are not limited to: detention and retention basins; open channels; storm sewers; pipes; and infiltration facilities.

Stormwater Management Site Plan – The plan prepared by the developer or his representative indicating how stormwater runoff will be managed at the development site in accordance with this Ordinance. **Stormwater Management Site Plan** will be designated as **SWM Site Plan** throughout this Ordinance.

Subdivision – As defined in The Pennsylvania Municipalities Planning Code, Act of July 31, 1968, P.L. 805, No. 247.

Total Maximum Daily Load (TMDL) – the sum of individual waste load allocations for point sources, load allocations for nonpoint sources and natural quality, and a margin of safety expressed in terms of mass per time, toxicity, or other appropriate measures. (25 Pa. Code § 96.1)

Urbanized Area (UA) – Land area comprising one or more places (central place(s)) and the adjacent densely settled surrounding area (urban fringe) that together have a residential population of at least 50,000 and an overall population density of at least 1,000 people per square mile, as defined by the United States Bureau of the Census and as determined by the latest available decennial census. The UA outlines the extent of automatically regulated areas.

Wasteload Allocation (WLA) – The portion of a surface water's loading capacity that is allocated to existing and future point source discharges. (25 Pa. Code § 96.1)

Water Quality Criteria – Numeric concentrations, levels, or surface water conditions that need to be maintained or attained to protect existing and designated uses. (25 Pa. Code § 93.1)

Water Quality Standards – The combination of water uses to be protected and the water quality criteria necessary to protect those uses. (25 Pa. Code § 92a.2)

Waters of this Commonwealth – Any and all rivers, streams, creeks, rivulets, impoundments, ditches, watercourses, storm sewers, lakes, dammed water, wetlands, ponds, springs, and all other bodies or channels of conveyance of surface and underground water, or parts thereof, whether natural or artificial, within or on the boundaries of this Commonwealth.

Watershed – Region or area drained by a river, watercourse, or other surface water of this Commonwealth.

Wetland – Areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support a prevalence of vegetation typically adapted for life in saturated soil conditions, including swamps, marshes, bogs, and similar areas.

USDA – United States Department of Agriculture.

ARTICLE III – STORMWATER MANAGEMENT STANDARDS

Section 301. General Requirements

- A. Regulated Activities are subject to the following permitting requirements:
1. Regulated Activities that involve proposal of less than 10,000 square feet of impervious surface, where the total cumulative impervious added since November 23, 2011 is less than 10,000 square feet, and where the disturbed area is less than 1 acre, may be exempted from portions of Article III (Stormwater Management Standards) including Section 303 (Volume Control) and Section 304 (peak rate control), and Article IV (SWM Site Plan requirements) including Section 408 (Financial Security) of this Ordinance. These Regulated Activities are considered Small Projects. For these activities the Applicant shall complete requirements as defined by the Small Project Approach (see Appendix D). The Regulated Activity shall be subject to all other requirements of this Ordinance other than related requirements for which an exemption or exemptions have been authorized.
 2. Regulated Activities that propose greater than 10,000 square feet of new impervious area shall be required to follow the requirements set forth in Article IV (SWM Site Plan Requirements)
 3. No Regulated Activities shall commence until the Municipality issues written approval of a SWM Site Plan or other applicable authorization which demonstrates compliance with the requirements of this Ordinance.
- B. SWM Site Plans approved by the Municipality, in accordance with Section 406 (Authorization to Construct and Term of Validity), shall be on-site throughout the duration of the Regulated Activity.
- C. The Municipality may, after consultation with DEP, approve measures for meeting the state water quality requirements other than those in this Ordinance, provided that they meet the minimum requirements of, and do not conflict with, state law including, but not limited to, the Clean Streams Law.
- D. For all Regulated Earth Disturbance Activities, erosion and sediment control BMPs shall be designed, implemented, operated, and maintained during the Regulated Earth Disturbance Activities (e.g., during construction beginning with initial topsoil removal and through the conversion and operation of all Post Construction Stormwater Management to meet the purposes and requirements of this Ordinance and to meet all requirements under Title 25 of the Pennsylvania Code and the Clean Streams Law. Various BMPs and their design standards are listed in the *Erosion and Sediment Pollution Control Program Manual* (E&S Manual³), No. 363-2134-008, as amended and updated.
- E. Impervious areas:
1. The measurement of impervious areas shall include all of the impervious areas in the total proposed development, even if development is to take place in stages.
 2. For development taking place in stages, the entire development plan must be used in determining conformance with this Ordinance.
 3. For projects that add impervious area to a parcel, the total impervious area on the parcel is subject to the requirements of this Ordinance; except that the volume controls in Section 303 and the peak rate controls of Section 304 do not need to be retrofitted to existing impervious areas that are not being altered by the proposed Regulated Activity.
- F. Stormwater flows onto adjacent property shall not be created, increased, decreased, relocated, or otherwise altered without written approval of the adjacent property owner(s). Such stormwater flows shall be subject to the requirements of this Ordinance.

- G. All Regulated Activities shall include such measures as necessary to:
1. Protect health, safety, and property.
 2. Meet the water quality goals of this Ordinance by implementing measures to:
 - a. Minimize disturbance to floodplains, wetlands, and wooded areas.
 - b. Maintain or extend riparian buffers.
 - c. Avoid erosive flow conditions in natural flow pathways.
 - d. Minimize thermal impacts to waters of this Commonwealth.
 - e. Disconnect impervious surfaces by directing runoff to pervious areas, wherever possible.
 3. Incorporate methods described in the *Pennsylvania Stormwater Best Management Practices Manual* (BMP Manual⁴). If methods other than green infrastructure and LID methods are proposed to achieve the volume and rate controls required under this Ordinance, the SWM Site Plan must include a detailed justification demonstrating that the use of LID and green infrastructure is not practicable.
- H. The design of all facilities over karst geology shall include an evaluation of measures to minimize adverse effects.
- I. Infiltration BMPs should be spread out such that impervious BMP loading ratios are less than or equal to 5:1, made as shallow as practicable, and located to maximize use of natural on-site infiltration features while still meeting the other requirements of this Ordinance.
- J. Unless designed as a retention pond with permanent ponding, storage facilities should completely drain both the volume control and rate control capacities over a period of time not more than 72-hours from the end of the design storm.
- K. The design storm precipitation depth to be used in the analysis of peak rates of discharge should be obtained from the latest version of the Precipitation-Frequency Atlas of the United States, National Oceanic and Atmospheric Administration (NOAA), National Weather Service, Hydrometeorological Design Studies, Center, Silver Spring, Maryland. NOAA's Atlas 145 can be accessed at: <http://hdsc.nws.noaa.gov/hdsc/pfds/>.
- L. For all Regulated Activities, SWM BMPs shall be designed, implemented, operated, and maintained to meet the purposes and requirements of this Ordinance and to meet all requirements under Title 25 of the Pennsylvania Code, the Clean Streams Law, and the Storm Water Management Act. Various BMPs and their design standards are listed in the BMP Manual⁴.
- M. Financial Security for the completion of stormwater management facilities is set forth in Section 407 and 408 of this Ordinance.

Section 302. Exemptions

- A. Agricultural activity is exempt from the SWM Site Plan preparation requirements of this Ordinance, provided the activities are performed according to the requirements of 25 Pa. Code Chapter 102.
- B. Forest management and timber operations are exempt from the SWM Site Plan preparation requirements of this Ordinance, provided the activities are performed according to the requirements of 25 Pa. Code Chapter 102.

- C. The use of land for domestic (i.e., for a single individual dwelling unit) gardening and landscaping is exempt from specific approval and permitting under this Ordinance so long as such activities comply with all other applicable ordinances and statutes.
- D. Exemptions from any provisions of this Ordinance shall not relieve the Applicant from the requirements in Sections 301.D. through L.
- E. The Municipality may deny or revoke any exemption pursuant to this Section at any time for any project that the Municipality believes may pose a threat to public health and safety or the environment.

Section 303. Volume Controls

Green Infrastructure and Low Impact Development practices provided in the BMP Manual⁴ shall be utilized for all Regulated Activities wherever possible. Water volume controls shall be implemented using the *Design Storm Method* in Subsection A or the *Simplified Method* in Subsection B below. This ordinance establishes that only the *Design Storm Method* may be used for Regulated Activities that add greater than one-half (1/2) acre of new impervious area or disturb greater than one acre of total area.

- A. The *Design Storm Method* (CG-1 in the BMP Manual⁴) is applicable to any size of Regulated Activity. This method requires detailed modeling based on site conditions, as verified through design phase soil infiltration testing.
 - 1. Do not increase the post-development total runoff volume for all storms equal to or less than the 2-year, 24-hour duration precipitation.
 - 2. For modeling purposes:
 - a. Existing (predevelopment) non-forested pervious areas must be considered meadow in good condition.
 - b. 20% of existing impervious areas to be disturbed by the project, when present, shall be considered meadow in good condition in the model for existing conditions. Regulated Activities not requiring an NDPES Permit are exempt from this requirement.
- B. The *Simplified Method* (CG-2 in the BMP Manual⁴) provided below is independent of site conditions and should be used if the *Design Storm Method* is not followed. This method is not applicable for Regulated Activities that add greater than one-half (1/2) acre of new impervious area. For new impervious surfaces:
 - 1. Stormwater facilities shall capture and store the first two (2) inches of runoff from all new impervious surfaces.
 - 2. At least the first one inch of runoff from new impervious surfaces shall be permanently removed from the runoff flow, i.e., it shall not be released into the surface waters of this Commonwealth. Removal options include reuse, evaporation, transpiration, and infiltration.
 - 3. Wherever possible, infiltration facilities should be designed to accommodate infiltration of the entire permanently removed runoff; however, in all cases, at least the first 0.5 inch of the permanently removed runoff should be infiltrated.
 - 4. Volume not infiltrated or otherwise permanently removed (up to 1") shall be detained using BMPs and released at a controlled rate.

Section 304. Rate Controls

- A. For computation of pre-development peak discharge rates, 20% of existing impervious areas to be disturbed by the project, when present, shall be considered meadow. Regulated Activities not requiring an NDPES Permit are exempt from this requirement.
- B. Post-development discharge rates shall not exceed the pre-development discharge rates for the 1-, 2-, 5-, 10-, 25-, 50-, and 100-year, 24-hour storm events. If it is shown that the peak rates of discharge indicated by the post-development analysis are less than or equal to the peak rates of discharge indicated by the pre-development analysis for 1-, 2-, 5-, 10-, 25-, 50-, and 100-year, 24-hour storms, then the requirements of this section have been met. Otherwise, the Applicant shall provide additional controls as necessary to satisfy the peak rate of discharge requirement.

Section 305. Riparian Buffers

- A. If a Riparian Buffer is proposed as a BMP for water quality or volume control, an easement over the Riparian Buffer shall be created and recorded.
- B. Minimum Management Requirements for Riparian Buffers.
 - 1. Existing native vegetation shall be protected and maintained within the Riparian Buffer Easement.
 - 2. Whenever practicable invasive vegetation shall be actively removed, and the Riparian Buffer Easement shall be planted with native trees, shrubs, and other vegetation to create a diverse native plant community appropriate to the intended ecological context of the site.
- C. The Riparian Buffer Easement shall be enforceable by the municipality and shall be recorded in the appropriate County Recorder of Deeds Office so that it shall run with the land and shall limit the use of the property located therein. The easement shall allow for the continued private ownership and shall count toward the minimum lot area required by Zoning unless otherwise specified in the Municipal Zoning Ordinance.
- D. Any permitted use within the Riparian Buffer Easement shall be conducted in a manner that will maintain the extent of the existing 100-year floodplain, improve or maintain the stream stability, and preserve and protect the ecological function of the floodplain.
- E. The following conditions shall apply when public and/or private recreation trails are permitted within Riparian Buffers:
 - 1. Trails shall be for non-motorized use only.
 - 2. Trails shall be designed to have the least impact on native plant species and other sensitive environmental features.
- F. Septic drain fields and sewage disposal systems shall not be permitted within the Riparian Buffer Easement and shall comply with setback requirements established under 25 Pa. Code Chapter 73.
- G. Use of Riparian Buffers to satisfy volume control requirements may be considered on an individual basis. If use of Riparian Buffers to satisfy volume control requirements is permitted, parameters for establishing the Riparian Buffer, provided by the municipality, shall be met.

Section 306. Design Criteria

- A. *Off-Site Areas.* Off-site areas which drain through a proposed development site are not subject to release rate criteria when determining allowable peak runoff rates. However, on-site drainage facilities shall be designed to safely convey off-site flows through the development site for the one hundred (100) year storm.
- B. *On-Site Areas.* On-site areas proposed to remain undisturbed as part of the Regulated Activity, including previously developed areas, shall be considered as existing conditions.
- C. *Downstream Hydraulic Capacity Analysis.* The downstream capacity hydraulic analysis shall be conducted in accordance with this Ordinance.
 - 1. All downstream facilities impacted by the total site area of the regulated facility shall be studied to determine if the facility has adequate capacity to handle existing and proposed flows. An impacted downstream facility is one to which the runoff from the total site area of the Regulated Activity comprises more than 50% of the total flow to such a facility. The study shall end at a perennial stream unless directed otherwise by the Municipal Engineer. Downstream facilities include, but are not limited to, man-made or natural swales and open channels, pipes, inlets, culverts, bridges, and roadways.
 - 2. If any facility is found to be undersized, the Applicant shall be responsible for evaluating the impact of the Regulated Activity and mitigating any negative impacts.
- D. *Regional Detention Alternatives.* For certain areas within the study area, it may be more cost-effective to provide one control facility for more than one development site than to provide an individual control facility for each development site. The initiative and funding for any regional runoff control alternatives are the responsibility of prospective developers. The design of any regional control basins must incorporate reasonable development of the entire upstream watershed. The peak outflow of a regional basin would be determined on a case-by-case basis using the hydrologic model of the watershed consistent with the protection of the downstream watershed areas. "Hydrologic model" refers to the calibrated model as developed for the stormwater management plan.
- E. Capacity improvements may also be provided as necessary to implement any regional or sub-regional detention alternatives.
- F. *Watershed Integrity.* Stormwater runoff shall not be transferred from one watershed to another unless the watersheds are sub-watersheds of a common watershed that join together within the perimeter of the property. The transfer of watersheds may be permitted in the event the transfer does not alter the peak discharge onto downstream lands, or drainage easements are acquired from the affected landowners.
- G. *Design Standards –Collection Systems*
 - 1. Storm sewer pipes, other than those used for street subbase underdrains, shall have a minimum diameter of fifteen (15") inches. Structural calculations that address the actual design requirements will be required where installation conditions merit.
 - 2. Storm Sewer Pipes and culverts shall be installed with a minimum slope of one-half (0.5%) percent.
 - 3. Allowable pipes, culvert, and bridge materials shall be as outlined in the Municipality's Construction and Material Specifications

4. All storm sewer crossings and culvert crossings of streets shall not deviate by more than fifteen (15°) degrees from perpendicular to the street centerline.
5. Design storm frequency to be used for:
 - a. All storm sewer pipes, culverts, bridges, gutters, and swales (excluding outfall structures from stormwater management facilities) conveying water originating only from within the boundaries of the project site shall be designed for a twenty-five (25) year storm event.
 - b. All storm sewer pipes, culverts and bridges, gutters, and swales conveying water originating from off-site shall be designed for a fifty-(50) year storm event with provisions to pass the one-hundred (100) storm safely through the site.
 - c. Culverts under sole access drives or streets to a developed property shall be designed to convey the One-Hundred-(100) Year storm event without roadway overtopping.
 - d. Drainage and access easements shall be provided to encompass the water surface limits of the One-Hundred (100) Year storm event throughout the project site and to provide access from a public street to the stormwater facility. Easements shall begin at the furthest upstream property line of the proposed development in the watershed.
 - e. When a pipe or culvert is intended to convey the discharge from a stormwater management facility, its required capacity shall be computed by the rational method and compared to the peak outflow from the stormwater facility for the 100-year storm. The greater flow shall govern the design of the pipe or culvert.
 - f. When a pipe is part of a storm sewer system and crosses the roadway, it shall be designed as a storm sewer with the same design storm as the remainder of the drainage system.
 - g. A 100-year storm frequency may be required for the design of the stormwater collection system to ensure that the runoff from the post-development storm is directed into the intended management facility.
 - h. Proposed channels or swales must be able to convey the increased runoff associated with a proposed 100-year return period event within their banks at velocities consistent with protection of the channels from erosion. Acceptable velocities shall be based upon criteria included in the PADEP *Erosion and Sediment Pollution Control Program Manual* (E&S Manual³).
6. All storm sewer pipes and culverts shall be laid to a minimum depth of twelve (12") inches from finished subgrade to the crown of the pipe in paved and grassed areas, or more if specified by the manufacturer.
7. Curves or angle points in pipes or box culverts without the use of an inlet or manhole are prohibited unless pre-approved by the Municipality. Tee joints, elbows, and wyes shall be limited for use in constructing underground detention facilities, underground retention facilities, underdrain systems, and roof leader collection systems.
8. Pipe connections to box structures shall not penetrate through the corner of the box.
9. Manholes, inlets, headwalls, endwalls, and end sections shall conform to the requirements of the PennDOT, Publication 408.

10. Inlets shall be:
 - a. placed on both sides of the street at low spots;
 - b. at a maximum of six hundred (600') feet apart along a storm sewer pipe run, and at points of abrupt changes in the horizontal or vertical directions of storm sewers;
 - c. shall normally be along the curb line at or beyond the curb radius points;
 - d. within the street right-of-way;
 - e. designed with a maximum gutter spread (based on the twenty-five (25) year storm event) no greater than one-half (1/2) of the travel lane width and have a maximum depth of three (3") inches at the curb line, a parking lane shall not be considered as part of the travel lane;
 - f. designed at intersections and access driveways to allow the depth of flow to be less than one and one-half (1-1/2) inches (for the twenty-five (25) year storm event);
 - g. in general, spaced such that, based upon the rational method, $t_c = 5$ min. and 10-year rainfall intensity, the area contributing to the inlet shall not produce a peak runoff of greater than 4 cfs. Also, inlets shall be spaced so that their efficiency, based upon efficiency curves published by the Pennsylvania Department of Transportation, is not less than sixty-five (65%) percent.
11. Flow velocities from any storm sewer may not result in erosion of the receiving channel. Adequate erosion protection shall be provided along all open channels and at all points of discharge.
12. All other storm sewer manholes and inlets shall have smooth flow lines grouted.
13. Headwalls and endwalls shall be used where stormwater runoff enters or leaves the storm sewer horizontally from a natural or man-made channel. In all cases where drainage is picked up by means of a headwall, the pipe shall be designed as a culvert. Inlet and outlet conditions shall be analyzed. PennDOT type "dw" headwalls and endwalls shall be utilized for pipes fifteen (15") inches and larger in diameter. End sections shall be utilized for pipes smaller than fifteen (15") inches in diameter. An entrance condition analysis must be performed according to PennDOT Publication 13M, Chapter 10-Drainage Design and Related Procedures.
14. Guards shall be provided on all intake and outfall structures as well as outlet structures. The guard bars shall be 1/2-inch diameter galvanized bars on 6-inch centers attached to the structure with 3/8-inch diameter stainless steel anchors. Guards shall also be provided for any pipe opening, eighteen (18") inches in diameter or larger.
15. For all swales, capacities, and velocities shall be computed using the Manning Equation. The following design considerations shall be met:
 - a. Two analyses of channel velocity and stability shall be provided with each swale design. One analysis shall be based upon the swale in an unvegetated state with control matting, and the second shall consider the channel in permanent, designed conditions.
 - b. All swales shall have a minimum slope of one (1%) percent unless otherwise approved by the Municipal Engineer.
16. Placement or use of BMPs within the public street right-of-way shall be prohibited.

H. Design Standards – General BMP regulations:

1. The design of all BMP facilities shall incorporate best engineering practices. The design engineer shall utilize all available design criteria in the BMP Manual to meet the requirements of this ordinance and shall provide all the necessary backup documentation with their submittal.
2. The BMPs must be designed to protect and maintain existing uses and maintain the level of Water Quality necessary to protect those uses in all streams, and to protect and maintain Water Quality in “Special Protection” streams, as required by statewide regulations at 25 Pa. Code Chapter 93.
3. No Regulated Earth Disturbance Activities within the Municipality shall commence until approval by the Municipality of a plan that ensures post-construction stormwater discharges do not degrade the physical, chemical, or biological characteristics of the receiving waters.

I. Design Standards - Subsurface Infiltration Facilities:

1. Positive overflow must be provided in the subsurface infiltration facility. Overflow structures or pipes must be designed to convey the inflow capacity of the facility. Volume control credits may not be used above the lowest invert of the positive overflow structure or pipe.
2. The minimum allowable distance between a subsurface infiltration facility and structure/building/retaining wall is ten (10') feet.
3. The subsurface infiltration facility must be located at least two feet above any limiting zone, i.e., seasonal high groundwater table, bedrock, or poorly infiltrating soils.
4. Soils with rates exceeding ten (10") inches per hour require soil amendments. During construction, upon reaching the subgrade of the infiltration facility, a two-foot thick layer of soil amendments must be spread across the entire facility bottom area, below the designed bottom of the facility. Soil media infiltration rate must be provided upon design.
5. The infiltration facility must include an acceptable form of pretreatment before stormwater enters the facility.
6. Subsurface Infiltration Facilities may not use a geotextile liner to separate the storage area from the subgrade. Geotextile liners may only be used on the sides and top. AASHTO Class 1 or Class 2 geotextile is recommended.
7. Subsurface Infiltration facilities must contain a cleanout or observation well at the end of any portion of underdrain. The observation well or cleanout must be placed at the invert of the stone bed and extend up to grade. Adequate inspection and maintenance access to the observation well or cleanout must be provided.
8. In subsurface infiltration facilities that include chamber, pipe, or other storage systems, a sufficient number of access features must be provided to efficiently inspect and maintain the infiltration area.
9. Perforated distribution pipes must contain a bedding of at least 4" separating the pipe and subgrade.
10. Infiltration Testing standards set forth in Appendix B shall be followed when designing a subsurface infiltration facility.

J. Design Standards; Detention and Retention Basins.

1. Permanent detention and retention basins shall be designed to meet the following standards:

- a. All above ground retention and detention facilities shall be designed with storage depths below two feet (2') whenever possible and unless the Applicant can demonstrate the need and justification for a facility to be constructed with a storage depth greater than two feet (2'). Justification for facilities greater than two feet (2') shall be approved by the Township Supervisors. Justification shall take into consideration public safety hazards such as proximity to existing or potential residential developments or other developments that would expose public to safety risks. Any facility that is designed and approved to store greater than two feet in depth shall be subject to the following requirements:
 - i. In no case shall the detention or retention basin be greater than six feet (6') measured from the bottom of the emergency spillway to the lowest point in the basin.
 - ii. If an above-ground facility is permitted to have storage depth over two feet (2') the facility shall be completely surrounded by a fence not less than four feet (4') in height with maximum of four-inch (4") openings.
 - (a) The fence type and style shall be reviewed and approved at the discretion of the Township. The Township may require or approve the installation of a shrub barrier in lieu of a fence. The Township reserves the right to review and approve the proposed shrubbery for this application.
 - (b) When fences are approved, all gates or doors opening through such enclosure shall be equipped with self-closing and self-latching devices for keeping the gate or door securely closed at all times, when not in actual use.
- b. The maximum permitted inside side-slopes for detention or retention basins shall be 4 to 1 vertical. 3 to 1 vertical inside side-slopes may be approved upon furnishing an appropriate planting schedule. The maximum permitted outside side-slopes shall be 3 to 1 vertical and utilize a seed mix designed for embankments. Areas for vehicle access shall be provided and encompassed by a 20' wide easement and shall have slopes no greater than 5 to 1 vertical. The proposed vegetation shall be low-maintenance varieties.
- d. Any stormwater management facility (i.e., detention basin) designed to store runoff and requiring a berm or earthen embankment required or regulated by this Ordinance shall be designed to provide an emergency spillway to handle flow up to and including the 100-year, 24-hour design storm at post-development conditions, assuming the principal outlet structure to be clogged. The height of the embankment must be set as to provide a minimum of one (1') foot of freeboard above the maximum elevation computed. Should any stormwater management facility require a dam safety permit under PADEP 25 Pa.Code, Chapter 105, the facility shall be designed in accordance with PADEP 25 Pa.Code, Chapter 105, and meet the regulations of PADEP 25 Pa.Code, Chapter 105, concerning dam safety which may be required to pass storms larger than the 100-year event.
- e. A cutoff trench composed of impervious material, four feet (4') minimum in width, shall be provided within all basin embankments. The top of the cutoff trench should be six inches (6") from the spillway elevation.
- f. Where a basin embankment is constructed using fill on an existing fifteen (15%) percent or greater slope, the basin must be keyed into the existing grade.

- h. All outlet structures and emergency spillways shall include a non-erosive means of energy dissipation at its outlet to assure conveyance and flow without endangering the safety and integrity of the basin and the downstream drainage area.
- i. Plans for infiltration must show the locations of existing and proposed septic tank infiltration areas and wells. A minimum 25-foot separation from on-lot disposal systems (OLDS) infiltration areas, including replacement areas, is desired and will be evaluated by the Municipality on a case-by-case basis. However, the separation shall not be less than the PADEP required 10 feet. Infiltration rates shall be based upon perc and probe tests conducted at the site of the proposed facility.
- j. Above-ground infiltration facilities shall provide a means of emergency dewatering of the facilities to the bottom elevation. If amended soils are used in the facility bottom, an underdrain shall be placed below or at the bottom of the amended soils to dewater the amended soils in emergency situations.

K. Design Standards; Rain Gardens/ Bioretention Facilities.

- 1. A rain garden/bioretention facility is an excavated shallow surface depression or storage area created by an earthen embankment in which amended soils are planted with specific native vegetation to treat and capture runoff. Rain gardens shall meet the following design standards (note: any SWM facility exceeding these design standards shall be considered a retention/detention basin and subject to their design standards):
 - a. The maximum ponding depth shall be twelve (12") inches.
 - b. Infiltration Testing standards set forth in Appendix C shall be followed when designing a rain garden facility.
 - c. The bottom of the rain garden storage area must be located at least two feet above any limiting zone, i.e., seasonal high groundwater table, bedrock, or poorly infiltrating soils.
 - d. Pretreatment shall be used in the design of the facility. Pretreatment can include structures such as sumped and trapped inlets, sediment/grit chambers or separators, media filters, inlet inserts, or other appropriate prefabricated or proprietary designs to remove sediment, floatables, and/or hydrocarbons from stormwater runoff prior to being conveyed to a rain garden/bioretention basin. A facility may be exempt from pretreatment at the discretion of the municipal engineer.
 - e. Maximum side slopes for surface storage areas shall be 4(H):1(V).
 - f. Any stone storage systems incorporated into the rain garden design must be separated from the soil media by a geotextile liner. A geotextile liner shall not be used to separate the stone storage system from the subgrade. Stone storage systems shall have a level bottom or use a terraced system if installed along a slope.
 - g. In the event a sand layer is to be used as part of the underground filtration/storage system. The sand must be placed between the soil medium and stone storage. All sides of the sand must be separated by a geotextile liner.

- h. The planting soil medium must have a minimum depth of eighteen (18") inches. Planting soil shall be a loam soil capable of supporting a healthy vegetative cover. Soils shall be amended with a composted organic material. At a minimum, the organic amended soil shall be combined with 20-30% organic material (compost) and 70-80% soil base (topsoil) free of clay. Amended soils shall be spread throughout the bottom floor of the facility.
- i. Underdrains must be provided for all rain gardens and extend throughout the entire rain garden bottom. Underdrains must be surrounded by a stone layer with a minimum of four (4") inches above and below the pipe.
- j. Rain Gardens that are used for volume control credits shall have an underdrain with a valve that is to remain closed at all times unless dewatering the facility to perform maintenance.
- k. A sufficient number of cleanouts must be provided to access underdrains to allow for maintenance and inspection of the underdrain pipe.
- l. Native plants shall be utilized and capable of supporting the proposed ponding depth. The designer shall refer to the PA DEP BMP manual for a list of potential native plant species.

Section 307. Regulations Governing SWM Facilities

- A. Any stormwater facility located on State highway rights-of-way shall be subject to approval by the Pennsylvania Department of Transportation (PennDOT).
- B. Any stormwater management facilities regulated by this Ordinance that would be located in or adjacent to waters of the Commonwealth or wetlands shall be subject to approval by PADEP through the joint permit application process or, where deemed appropriate by PADEP, the general permit process. When there is a question of whether wetlands may be involved, it is the responsibility of the developer or his agent to show that the land in question cannot be classified as wetlands; otherwise, approval to work in the area must be obtained from PADEP.
- C. Any stormwater management facility located within the vicinity of a floodplain shall be subject to approval in accordance with PADEP 25 Pa.Code, Chapter 105, "Floodplain Management," of PADEP's rules and regulations and the municipal floodplain management regulations.
- D. The design of all stormwater management facilities shall incorporate good engineering principles and practices. The Municipality shall reserve the right to disapprove any design that would result in the occupancy or continuation of adverse hydrologic or hydraulic conditions within the watershed.
- E. The existing points of concentrated drainage that discharge onto adjacent property shall not be altered without permission of the adjacent property owner(s) and shall be subject to any applicable discharge criteria specified in this Ordinance. New proposed discharge points shall be no closer than 10' to the property line in which they are located.
- F. Areas of existing diffused drainage discharge shall be subject to any applicable discharge criteria in the general direction of existing discharge, whether proposed to be concentrated or maintained as diffused drainage areas, except as otherwise provided by this Ordinance. If the diffused flow is proposed to be concentrated and discharged onto adjacent property, the developer must document that adequate downstream conveyance facilities exist to safely transport the concentrated discharge or otherwise prove that no erosion, sedimentation, flooding, or other harm will result from the concentrated discharge.

- G. Where a development site is traversed by watercourses, 20' wide minimum drainage easements (10' from top of the bank out) shall be provided conforming to the line of such watercourses. The terms of the easement shall prohibit excavation, the placing of fill or structures, and any alterations that may adversely affect the flow of stormwater within any portion of the easement. Also, maintaining of vegetation in a natural state within the easement shall be required, except as approved by the appropriate governing authority.
- H. When it can be shown that, due to topographic conditions, natural drainage ways on the site cannot adequately provide for drainage, open channels may be constructed conforming substantially to the line and grade of such natural drainage ways. Work within natural drainage ways shall be subject to approval by PADEP through the joint permit application process or, where deemed appropriate by PADEP, through the general permit process.
- I. Roof drains and sump pumps shall discharge to lawns, infiltration or vegetative BMPs, or pervious area to promote overland flow and infiltration/percolation wherever/whenever possible. If the above discharge criteria cannot be met or when it is more advantageous to connect directly to streets, storm sewers or other stabilized conveyance designations, then the discharge will be permitted on a case-by-case basis by the Municipality. All discharges shall be conveyed in a manner so as to not cause water problems on adjoining property owners without written approval.
- J. *Special Requirements for Areas Falling Within Defined Exceptional Value and High-Quality Subwatersheds.* The temperature and quality of water and streams that have been declared as exceptional value and high quality are to be maintained as defined in 25 Pa.Code, Chapter 93, "Water Quality Standards," Pennsylvania Department of Environmental Protection rules and regulations. Temperature-sensitive BMP's and stormwater conveyance systems are to be used and designed with storage pool areas and supply outflow channels and should be shaded with trees. This will require modification of berms for permanent ponds and the relaxation of restrictions on planting vegetation within the facilities, provided that capacity for volumes and rate control is maintained. At a minimum, the southern half on pond shorelines shall be planted with shade or canopy trees within 10 feet of the pond shoreline. In conjunction with this requirement, the maximum slope allowed on the berm area to be planted is 10 to 1. This will lessen the destabilization of berm soils due to root growth. A long-term maintenance schedule and management plan for the thermal control BMPs are to be established and recorded for all development sites within defined exceptional value and/or high-quality subwatersheds.
- K. The use of soil amendment, or amended soil shall not be utilized within the yard area or building envelope of a lot unless approved by the Municipal Engineer or unless the soil amendment is a component of the BMP facilities design such as the use of soil amendment within infiltration basins or rain gardens.
- L. No SWM facilities shall be installed over existing utility mains or services.

Section 308. Calculation Methodology

- A. Stormwater runoff from all development sites shall be calculated using the rational method, modified rational method, or a soil cover complex methodology.
 - 1. Any stormwater runoff calculations involving drainage areas greater than two-hundred (200) acres, including on- and off-site areas, shall use generally accepted calculation technique that is based on the NRCS soil cover complex method. It is assumed that all methods will be selected by the design professional based on the individual limitations and suitability of each method for a particular site.

2. The Municipality may allow the use of the rational method or modified rational method to estimate peak discharges from drainage areas that contain less than two hundred (200) acres. When using the rational method, an ascending and descending limb factor of 3 and 7 shall be used, respectively.
3. All calculations consistent with this Ordinance using the soil cover complex method shall use the appropriate design rainfall depths. If a hydrologic computer model such as PSRM or HEC-RAS is used for stormwater runoff calculations, then the duration of rainfall shall be 24-hours. The SCS Rainfall Type II curve shall be used for the rainfall distribution. Those projects proposing infiltration structures shall utilize this method.
4. When routing a detention basin, the rational method or SCS method may be used to determine peak rates through the primary outlet structure. Only the SCS Method may be used to determine the peak water surface elevation during the 100-year, 24-hour design storm, dictating the height of the embankment.
5. Underground Storage Facilities that solely receive stormwater and are designed to capture and infiltrate the entire 100-year, 24-hour SCS runoff volume may have their drainage areas removed from the overall post-development drainage area(s).
6. For the purposes of pre-development flow rate determination, undeveloped land, including disturbed areas, shall be considered as "meadow" in good condition, unless the natural ground cover generates a lower curve number or rational "C" value (i.e., forest), as listed in Tables 1 and 2, respectively.
7. All calculations using the rational method shall use rainfall intensities consistent with appropriate times of concentration for overland flow and return periods. Times of concentration for overland flow shall be calculated using the methodology presented in Chapter 3 of *Urban Hydrology for Small Watersheds*, NRCS, TR-55 (as amended or replaced from time to time by NRCS). Time of concentration for channel and pipe flow shall be computed using Manning's equation.
8. Runoff curve numbers (CN) for both existing and proposed conditions to be used in the soil cover complex method shall be obtained from Table 1.
9. Runoff coefficients (c) for both existing and proposed conditions for use in the rational method shall be obtained from Table 2.
10. Where uniform flow is anticipated, the Manning equation shall be used for hydraulic computations such as the capacity of open channels, pipes, and storm sewers. Values for Manning's roughness coefficient (n) shall be consistent with Table 3.
11. The design of any stormwater detention facilities intended to meet the performance standards of this Ordinance shall be verified by routing the design storm hydrograph through these facilities, using either manual methods or computerized routing. Routing shall be based upon the modified PULS method; other routing methodologies shall be subject to the approval of the Municipal Engineer.
12. The stormwater collection system shall be designed using the peak discharge computed using the rational formula.

Section 309. Carbonate Geology

In areas of carbonate geology, a geologist shall certify to the following:

- A. No stormwater management facility will be placed in, over, or immediately adjacent to the following features:
 - 1. Closer than 100 feet from sinkholes;
 - 2. Closer than 100 feet from closed depressions;
 - 3. Closer than 100 feet from caverns, intermittent lakes, or ephemeral streams;
 - 4. Closer than 50 feet from lineaments in carbonate areas;
 - 5. Closer than 50 feet from fracture traces;
 - 6. Closer than 25 feet from bedrock pinnacles (surface or subsurface).
- B. Stormwater resulting from Regulated Activities shall not be discharged into sinkholes.
- C. If the developer can prove through analysis that the project site is an area underlain by carbonate geology, and such geologic conditions may result in sinkhole formations, then the project site is exempt from recharge requirements as described in Section 304, "Volume Control." However, the project site shall still be required to meet all other standards found in this Ordinance.
- D. It shall be the developer's responsibility to verify if the project site is underlain by carbonate geology. The following note shall be attached to all stormwater management plans and signed and sealed by the developer's registered professional: "I, _____, certify that the proposed stormwater management facility (circle one) is/is not underlain by carbonate geology."
- E. Whenever a stormwater management facility will be located in an area underlain by carbonate geology, a geological evaluation of the proposed location by a geologist shall be conducted to determine susceptibility to sinkhole formation. The evaluation may include the use of impermeable liners to reduce or eliminate the separation distances listed in the BMP manual. Additionally, the evaluation shall, at a minimum, address soil permeability, depth to bedrock, seasonally high groundwater table, susceptibility for sinkhole formation, suitability of stormwater management facilities, subgrade stability, and maximum infiltration capacity in depth of water per unit area.
- F. A detailed soils evaluation of the project site shall be performed to determine the suitability of recharge facilities. The evaluation shall be performed by a qualified professional, and at a minimum, address soil permeability, depth to bedrock, susceptibility to sinkhole formation, and subgrade stability. The general process for designing the infiltration BMP shall be:
 - 1. Site evaluation to determine general areas of suitability for infiltration practices.
 - 2. Provide field percolation tests throughout the area proposed for development to determine appropriate percolation rate and/or hydraulic conductivity. At least one infiltration test must be included in each soil group, and at least one infiltration test must be conducted for every five lots proposed for development. Infiltration tests must be taken at the location and depth of all proposed infiltration structures.
 - 3. Design infiltration structure for required storm volume based on all available data.

- G. Extreme caution shall be exercised where infiltration is proposed in geologically susceptible areas such as strip mine or limestone areas. It is also extremely important that the design professional evaluate the possibility of groundwater contamination from the proposed infiltration/recharge facility and recommend a hydrogeologic study be performed if necessary. Whenever a basin is located in an area underlain by limestone, a geological evaluation of the proposed location shall be conducted to determine susceptibility to sinkhole formations. The design of all facilities over carbonate formations shall include measures to prevent groundwater contamination and, where necessary, sinkhole formation. The infiltration requirement in the high quality/exceptional waters shall be subject to the Department's 25 Pa.Code, Chapter 93, and anti-degradation regulations. A detailed hydrogeologic investigation may be required by the Municipality, and where appropriate, the Municipality may require the installation of an impermeable liner in detention basins.

Section 310. Erosion and Sedimentation Control Requirements

- A. As required in Section 301.D, whenever the vegetation and topography are to be disturbed, such activity must be in conformance with PA Code Title 25, Environmental Protection, Part I, Subpart C, Article II, Chapter 102. Erosion and Sediment Control and in accordance with the County Conservation District.
- B. It is extremely important that strict erosion and sedimentation control measures be applied surrounding infiltration structures during installation to prevent the infiltrative surfaces from becoming clogged. Additional erosion and sedimentation control design standards and criteria must be applied where infiltration BMPs are proposed shall include the following:
1. Areas proposed for infiltration BMPs shall be protected from sedimentation and compaction during the construction phase so as to maintain their maximum infiltration capacity.
- C. Fencing for sedimentation basins or traps must comply with Section 308.
- D. The developer shall demonstrate that the post-development hydrograph flows during erosion and sedimentation control phase are less than or equal to the pre-development hydrograph flows to assure the rate and volume of runoff leaving the site is controlled for the 2-, 5-, and 10-year frequency storms. All calculation methodology shall be in accordance with Section 303 through 309.
- E. In the event a Regulated Activity falls under the Chapter 102 thresholds for requiring a written erosion and sedimentation plan and/or NPDES permit, the Applicant is still required to provide suitable erosion and sedimentation best management practices to prevent an illicit discharge caused by erosion during a precipitation event.

ARTICLE IV – STORMWATER MANAGEMENT (SWM) SITE PLAN REQUIREMENTS

Section 401. Plan Requirements

- A. Appropriate sections from the Municipality's Subdivision and Land Development Ordinance, and other applicable local ordinances, shall be followed in preparing the SWM Site Plans.
- B. The Municipality shall not approve any SWM Site Plan that is deficient in meeting the requirements of this Ordinance. At its sole discretion and in accordance with this Article, when a SWM Site Plan is found to be deficient, the Municipality may either disapprove the submission and require a resubmission, or in the case of minor deficiencies, the Municipality may accept the submission of modifications.
- C. Provisions for permanent access or maintenance easements for all physical SWM BMPs, such as ponds and infiltration structures, as necessary to implement the operation and maintenance (O&M) plan, shall be provided as follows:
 1. A minimum twenty (20') foot wide drainage easement shall be provided for all stormwater management facilities. Drainage easements shall provide for ingress and egress to a public right-of-way.
 2. A minimum twenty (20') foot wide drainage easement shall be provided where the conveyance, treatment, of stormwater, either existing or proposed, is identified on the stormwater management plan. Drainage easements shall be provided to contain and convey the One-Hundred (100) year storm event.
 3. A note on the stormwater management plan indicating that nothing shall be placed, planted, set, or put within the area of an easement that is not consistent with the approved plan. No alterations to swales, basins, BMPs, or other stormwater management shall be permitted without prior approval.
 4. Stormwater Management Facilities not located within a public right-of-way shall be contained in and centered within a drainage easement. Easements shall follow property boundaries where possible.
- D. The SWM Site Plan shall provide the following information:
 1. A written report including an overall project description of the proposed stormwater management concepts, including a summary identifying specific LID and Green Infrastructure practices and the existing site conditions. Including stormwater runoff calculations for both predevelopment and post-development conditions, including complete hydrologic, hydraulic, and structural computations for all stormwater management facilities.
 2. A determination of site conditions in accordance with the BMP Manual⁴. A detailed site evaluation shall be completed for projects proposed in areas of carbonate geology or karst topography and other environmentally sensitive areas, such as brownfields.
 3. All calculations, assumptions, and criteria used in the design of the stormwater management facilities must be shown. If multiple facilities are used in conjunction with each other, such as infiltration BMPs with vegetation-based management practices, a summary narrative shall be included describing any sequencing and how the facilities are meant to function with each other to manage stormwater runoff in accordance with this ordinance.

4. The plan sheet sizes shall be either 11 inches by 17 inches, 18 inches by 24 inches, 22 inches by 34 inches, or 24 inches by 36 inches. If the plan is prepared in two (2) or more drawing sheets, a full-size drawing and key map showing the location of the sheets and a match line shall be placed on each sheet. Each sheet shall be numbered to show the relationship to the total number of sheets in the plan set.
5. Proposed name or identifying title of project.
6. Name and address of the landowner and APPLICANT of the PROJECT SITE.
7. The limit of disturbance (LOD) shall be shown with its area labeled in square feet or acres.
8. The existing and proposed impervious areas labeled in square feet.
9. Plan date and date of the latest revision to the plan.
10. North point.
11. Graphic scale and written scale. All plans shall be drawn at a scale sufficient to determine consistency with this and other municipal ordinances.
12. A table on the plan indicating the total acreage of the project site and the tract of land on which the project site is located, assumed square footage of impervious surface for each lot, and the assumed square footage of impervious surface permitted for each stormwater management facility.
13. A location map, for the purpose of locating the project site to be developed, at a minimum scale of 1,000 feet to the inch, showing the relation of the tract to adjoining property and to all streets and the Municipality boundaries existing within 400 feet of any part of the tract of land on which the project site is proposed to be developed.
14. A soil erosion and sediment control plan, where applicable, as prepared for and submitted to the approval authority as well as the Municipality.
15. The effect of the project (in terms of runoff volumes, water quality, and peak flows) on surrounding properties and aquatic features and on any existing stormwater conveyance system that may be affected by the project.
16. A hydrogeologic assessment of the effects of stormwater runoff on sinkholes, where present.
17. Plan and profile drawings of all SWM BMPs, including drainage structures, pipes, open channels, and swales. All plans and profiles should align vertically on the sheets for reference. All utility crossings shall be shown on these profiles.
18. SWM Site Plan shall show the locations of existing and proposed on-lot wastewater facilities and water supply wells.
19. The SWM Site Plan shall include an O&M Plan for all existing and proposed physical stormwater management facilities. This plan shall address long-term ownership and responsibilities for O&M as well as schedules and costs for O&M activities.
20. A justification must be included in the SWM Site Plan if BMPs other than green infrastructure methods and LID practices are proposed to achieve the volume, rate, and water quality controls under this Ordinance.

21. A description of permanent stormwater management techniques, including the construction specifications and the materials to be used for stormwater management facilities.
22. A notarized signature of the owner of the parcel for which the SWM site plan is proposed indicating that they are aware of and will be responsible for operation and maintenance of the facilities.
23. A list of all approved waivers to the stormwater management ordinance.
24. Existing features.
 - a. Tract boundaries showing distances, bearings, and curve data, as located by field survey or by deed plotting.
 - b. Existing contours at vertical intervals of one (1) or two (2) feet for land with an average natural slope of twenty (20) percent or less and at vertical intervals of five (5) feet for more steeply sloping land. The location of the benchmark and the datum used shall also be indicated.
 - c. The names of all owners of all immediately adjacent unplatted land and the locations and dimensions of any streets or easements shown thereon.
 - d. The names, locations, and dimensions of all existing streets, railroads, watercourses, drainage facilities, floodplains, streams, lakes, ponds, and other water bodies, existing drainage courses, Karst features, and other significant features within two hundred (200') feet of any part of the tract proposed to be developed and the location of all buildings and structures.
 - e. Other physical features including wetlands, sinkholes, areas of native vegetation to be preserved, including trees greater than two (2") inches in diameter at breast height, woodlands, other environmentally sensitive areas, and the total extent of the upstream area draining through the project site.
 - f. The locations of all existing utilities, including on-lot disposal systems and wells, sanitary sewers, and water lines within two hundred (200') feet of the property lines.
 - g. Soil boundaries and soil types as designated by the NRCS.
 - h. Existing zoning districts and property line setbacks.
 - i. A note on the plan identifying the presence or absence of carbonate geology. See Section 309. D. of this ordinance.
25. Proposed features.
 - a. The proposed land use, the number of lots and dwelling units, and the extent of commercial, industrial, or other non-residential uses.
 - b. The locations and dimensions of all proposed streets, parks, playgrounds, and other public areas, sewer and water facilities; lot lines and building locations; parking compounds, driveways, paved areas, and other impervious surfaces.
 - c. The proposed changes to land surface and vegetative cover, including areas to be cut or filled.
 - d. Proposed contours at vertical intervals of two (2') feet for land with an average natural slope of fifteen (15%) percent or less and at vertical intervals of five (5') feet for more steeply sloping land.

- e. Finished elevations on tops of curbs at lot lines projected and lot corners. Elevations shall be shown to the nearest tenth of a foot.
 - f. A summary table depicting the minimum lowest floor elevation, which includes the basement for all lots located immediately adjacent to the floodplain area.
 - g. The location of any proposed on-lot disposal system, replacement drainfield easements, and water supply wells.
 - h. The location of any proposed signage identifying the constructed BMP. Proposed signage shall be installed on any nonresidential property or property under the control of a homeowner's association or community association.
26. A summary table on the plan identifying all BMPs including BMP ID, drainage area to the BMP, name of receiving waterbody, the BMP's inspection and maintenance frequency, name of responsible person or organization at the time of stormwater management plan approval, and the lot numbers where the BMP is located.
27. The name of the development, the name and address of the owner of the property, and the name and address of the individual or firm preparing the plan. Also to be included are the name, address, signature, and seal of any registered surveyor, professional engineer, landscape architect, or professional geologist (for geomorphological assessments) contributing to and/or with a responsibility for any aspect of the plan where applicable.
28. A planting plan is required for all vegetated stormwater BMPs.
- a. Native or naturalized/non-invasive species suitable to the soil and hydrologic conditions of the site shall be used unless otherwise specified in the BMP Manual.
 - b. Invasive vegetation may not be included in any planting schedule. (See Invasive Plants in Pennsylvania as published by the Department of Conservation and Natural Resources.)
 - c. The limit of existing, native vegetation to remain shall be delineated on the plan along with proposed construction protection measures.
 - d. Prior to construction, a tree protection zone shall be delineated at the dripline of the tree canopy. The tree protection zone of trees scheduled to remain shall be marked. Groups of trees may be marked by a protection zone along the outermost drip line boundary. A forty-eight (48") inch high snow fence or forty-eight (48") inch high construction fence mounted on steel posts located eight (8') feet on center shall be placed along the tree protection boundary. No construction, storage of material, temporary parking, pollution of soil, or regrading shall occur within the tree protection zone.
 - e. All planting shall be performed in conformance with good nursery and landscape practice. Plant materials shall conform to the standards recommended in the American Standard of Nursery Stock.
 - 1. Planting designs are encouraged to share planting space for optimal root growth whenever possible.
 - 2. No staking or wiring of trees shall be allowed without a maintenance note requiring the stake and/or wire to be removed within one (1) year of planting.

Section 402. Plan Submission

- A. All materials submitted to the Municipality for review must be provided in PDF format.
- B. An application, provided by the Municipality shall be completed and submitted with the application fee, the SWM Site Plan, and the supporting report.
- C. Proof of NPDES Application and permit obtained (when required).
- D. Four (4) physical paper copies and two (2) electronic copy of the stormwater management site plan shall be submitted as follows, unless requested by the Municipality:
 - 1. Two (2) physical copies to the Municipality.
 - 2. One (1) physical copy to the Municipal Engineer (when applicable).
 - 3. One (1) physical copy to the County Conservation District (when applicable).
 - 4. One (1) electronic copy, submitted in a portable document format (PDF) to the Municipality.
 - 5. One (1) electronic copy, submitted in a portable document format (PDF) to the Municipal Engineer (when applicable).

Section 403. Plan Review

- A. SWM Site Plans shall be reviewed by the Municipality for consistency with the provisions of this Ordinance.
- B. From the time an application for approval of a plat involving a subdivision or land development plan, whether preliminary or final, which includes a SWM site plan, is duly filed with the Municipality, no change or amendment of the ordinance or other governing ordinance or plan shall affect the decision on such application in accordance with the provisions of the governing ordinances or plans as they stood at the time the application was duly filed, as specified in § 508(4)(i) of the Pennsylvania Municipalities Planning Code, 53 P.S. § 10508(4)(i).
- C. The Municipality shall notify the Applicant in writing within 45 days whether the SWM Site Plan is approved or disapproved. If the SWM Site Plan involves a Subdivision and Land Development Plan, the notification shall occur within the time period allowed by the Municipalities Planning Code (90 days). If a longer notification period is provided by another statute, regulation, or ordinance, the Applicant will be notified by the Municipality. If the Municipality denies approval of the SWM Site Plan, the Municipality will state the reasons for the denial in writing. The Municipality may also approve the SWM Site Plan with conditions and, if so, shall provide the acceptable conditions for approval in writing.
- D. For any SWM Site Plan that proposes to use any BMPs other than Green Infrastructure and LID practices to achieve the volume and rate controls required under this Ordinance, the Municipality will not approve the SWM Site Plan unless it determines that Green Infrastructure and LID practices are not practicable.

Section 404. Modification of Plans

Modifications to a submitted SWM Site Plan that involve a change in SWM BMPs or techniques, or that involves the relocation or redesign of SWM BMPs, or that is necessary because soil or other conditions are not as stated on the SWM Site Plan, as determined by the Municipality, shall require a resubmission of the modified SWM Site Plan in accordance with this Article.

- A. When reviewing a SWM site plan, whether or not the SWM site plan is included in a subdivision and/or land development plan application, the Municipality may, after consulting with DEP if over one (1) acre of disturbance, grant a modification of the requirements of one or more provisions of this Ordinance if the literal enforcement will enact undue hardship because of peculiar conditions pertaining to the land in question, provided that such modification will not be contrary to the public interest and that the purpose and intent of the ordinance are observed.
- B. All requests for a modification from an Applicant shall be in writing and shall accompany and be a part of the application for approval of a SWM site plan and/or a subdivision or land development plan as applicable. The request shall state in full the grounds and facts of unreasonableness or hardship on which the request is based, the provision or provisions of the ordinance involved, and the minimum modification necessary.
- C. In granting any modification, the Municipality may attach such reasonable conditions and safeguards as it may deem necessary to implement the purposes of the Act 167 Plan and this Ordinance.
- D. The Municipality shall keep a written record of all action on requests for modifications. The response of any consultation and/or review by DEP shall be included as an original report if available or otherwise documented in the required written record.

Section 405. Resubmission of Disapproved SWM Site Plans

A disapproved SWM Site Plan may be resubmitted, with the revisions addressing the Municipality's concerns, to the Municipality in accordance with this Article. The applicable review fee must accompany a resubmission of a disapproved SWM Site Plan.

Section 406. Authorization to Construct and Term of Validity

- A. *SWM Site Plans Independent of Subdivision and Land Development Plans.* The Municipality's approval of a SWM site plan, when such plan is submitted independent of a subdivision and/or land development plan, authorizes the Regulated Activities contained in the SWM site plan for a maximum term of validity of five (5) years following the date of approval. The Municipality may specify a term of validity shorter than five (5) years in the approval for any specific SWM site plan, particularly if the nature of the proposed SWM facilities require more frequent maintenance and/or short-term replacement of certain components. Terms of validity shall commence on the date the Municipality signs the approval for a SWM site plan. If an approved SWM site plan is not completed according to Section 407 within the term of validity, then the Municipality may consider the SWM site plan disapproved and may revoke any and all permits. SWM site plans that are considered disapproved by the Municipality may be resubmitted in accordance with Section 405 of this Ordinance.
- B. *SWM Site Plans Included in a Subdivision and/or Land Development Plan.* The Municipality's approval of a SWM site plan, which is a part of a subdivision and/or land development plan, authorizes that plan and the Regulated Activities therein so that no subsequent change or amendment in this Ordinance or other governing ordinances or plans shall be applied to affect adversely the right of the Applicant to commence and to complete any aspect of the approved development in accordance with the terms of such approval within five (5) years from such approval, as specified in § 508(4)(ii)-(vii) of the Pennsylvania Municipalities Planning Code, 53 P.S. § 10508(4)(ii)-(vii).

Section 407. As-Built Plans, Completion Certificate, and Final Inspection

- A. The developer shall be responsible for providing the Municipality with as-built plans of all SWM BMPs included in the approved SWM Site Plan. The as-built plans and an explanation of any discrepancies with the construction plans shall be submitted to the Municipality for review and approval.
- B. The as-built submission shall include a certification of completion signed by a qualified professional verifying that all permanent SWM BMPs have been constructed according to the approved plans and specifications. The latitude and longitude coordinates for all permanent SWM BMPs must also be submitted at the central location of the BMPs. If any licensed, qualified professionals contributed to the construction plans, then a licensed qualified professional must sign the completion certificate.
- C. After receipt of the completion certification by the Municipality, the Municipality may conduct a final inspection.
- D. The financial guarantee, as discussed under Section 408, shall not be released by the Municipality until the items in this Section are completed.

Section 408. Financial Security

- A. Unless exempted by Section 301.A.1 for Small Projects, the Applicant shall provide financial security to the Municipality to assure the timely installation and proper construction of all stormwater management facilities, including but not limited to erosion and sediment control measures and BMPs as required by the approved stormwater management plan and this ordinance. The posting and administration of financial security to guarantee the completion of required improvements and common amenities shall comply with the provisions of this Section, the Municipalities Planning Code (MPC), and other applicable laws of the Commonwealth.
- B. All financial security shall be prepared by the Applicant in the form required by the Municipality and in a form and content acceptable to the Solicitor for the Municipality. The amount of the security shall be calculated in accordance with Article V of the MPC. The following are acceptable forms of security. All other forms of security shall be individually approved by the Municipality.
 - 1. Letter of credit. A letter of credit provided by the Applicant from a financial institution or other reputable institution subject to the approval of the Municipality. This letter shall be deposited with the Municipality and shall certify the following:
 - a. That the creditor does guarantee funds in an amount equal to one hundred ten (110%) percent of the cost of completing all required improvements.
 - b. In case of failure on the part of the Applicant to complete the specified improvements within the required time period or notification by the financial institution that the letter of credit will not be renewed, the creditor shall pay to the Municipality immediately and without further action, such funds as are necessary to finance the completion of those improvements, up to the limit of credit stated in the letter.
 - c. The letter of credit may not be withdrawn or reduced in amount until released by the Municipality.
 - 2. Surety performance bond. A security bond from a surety bonding company authorized to do business in the Commonwealth of Pennsylvania. The bond shall be payable and in a form acceptable to the Municipality.

3. Escrow account. A deposit of cash with the Municipality or in escrow with a financial institution. The use of a financial institution for establishing an escrow account shall be subject to approval by the Municipality an agreement between the financial institution and himself guaranteeing the following:
 - a. That the funds of said escrow account shall be held in trust until released by the Municipality, as appropriate, and may not be used or pledged by the Applicant as security in any other manner during that period.
4. In the case of a failure on the part of the Applicant to complete said improvements, then the institution shall immediately make the funds in said account available to the Municipality for use in the completion of those improvements.
5. As the work of installing the required improvements proceeds, the party posting the financial security may request the Municipality to authorize the release of such portions of the financial security associated with the completed improvements. Requests for the partial release of financial security as the work of installing the required improvements proceeds shall be made and governed by the MPC.
6. At such time that the Applicant has completed and installed the required improvements, the elected officials shall consider the Applicant's request for a release from the improvement guarantee in accordance with the procedure set forth in the MPC.
7. At the completion of the project, and as a prerequisite for the release of the financial security, the Applicant shall provide record plans in accordance with Section 407.
8. Upon receipt of the Record Plans and prior to the release of the remaining financial security per Section 407.D, the Municipality shall conduct a final inspection to certify compliance with this ordinance.
9. In the event that any improvements which are required by this ordinance have not been installed as provided in this ordinance or in accordance with the approved stormwater management plan, the Municipality may enforce any corporate bond or other security by appropriate legal and equitable remedies. If proceeds of such bond or other security are insufficient to pay the cost of installing or making repairs or corrections to all the improvements covered by said security, the elected officials may, at their option, install part of such improvements in all or part of the stormwater management plan and may institute appropriate legal or equitable action to recover the monies necessary to complete the remainder of the improvements.

Article V - Construction Inspections

Section 501. Schedule of Inspections

- A. The Municipal Engineer or their assignee shall inspect phases of the installation of the permanent stormwater management facilities as deemed appropriate by the Municipal Engineer. It is the responsibility of the permittee to notify the Municipal Engineer 48 hours in advance of the beginning of construction of stormwater management facilities. Individual residential on-lot stormwater management systems shall be inspected by Municipal staff or appointed personnel.
- B. During any stage of the work, if the Municipal Engineer determines that the permanent stormwater management facilities are not being installed in accordance with the approved stormwater management plan, the Municipality shall revoke any existing approvals issued under this Ordinance until a revised drainage plan is submitted and approved, as specified in this Ordinance.
- C. All construction and materials shall correspond with the latest revision of the Municipality's Standard Construction and Material Specifications, as applicable.

ARTICLE VI – OPERATION AND MAINTENANCE

Section 601. Responsibilities of Developers and Landowners

Unless otherwise noted or if a facility is located within a municipal right of way, operation and maintenance of stormwater management facilities and conveyance systems is the sole responsibility of the property owner or assigns, in perpetuity.

- A. The Municipality shall make the final determination on the continuing maintenance responsibilities prior to final approval of the SWM Site Plan. The Municipality may require a dedication of such facilities as part of the requirements for approval of the SWM Site Plan. Such a requirement is not an indication that the Municipality will accept the facilities. The Municipality reserves the right to accept or reject the ownership and operating responsibility for any portion of the stormwater management controls.
- B. Facilities, areas, or structures used as SWM BMPs shall be enumerated as permanent real estate appurtenances and recorded as deed restrictions or conservation easements that run with the land.
- C. The O&M Plan shall be recorded as a restrictive deed covenant that runs with the land.
- D. No person shall modify, remove, fill, landscape, or alter any SWM BMPs, facilities, areas, or structures without the written approval of the Municipality, with the exception of necessary maintenance activities such as mowing.
- E. The Municipality may take enforcement actions against an owner for any failure to satisfy the provisions of this Article.

Section 602. Operation and Maintenance Agreements

- A. Prior to final approval of the SWM Site Plan, the property owner shall sign and record an Operation and Maintenance (O&M) Agreement (see Appendix A) covering all stormwater control facilities which are to be privately owned.
 - 1. The owner, successor, and assigns shall maintain all facilities in accordance with the approved maintenance schedule in the O&M Agreement.
 - 2. The owner shall convey to the Municipality conservation easements to assure access for periodic inspections by the Municipality and maintenance, as necessary.
 - 3. The owner shall keep on file with the Municipality the name, address, and telephone number of the person or company responsible for maintenance activities; in the event of a change, new information shall be submitted by the owner to the Municipality within ten (10) working days of the change.
- B. The owner is responsible for the operation and maintenance (O&M) of the SWM BMPs. If the owner fails to adhere to the O&M Agreement, the Municipality may perform the services required and charge the owner appropriate fees. Nonpayment of fees may result in a lien against the property.

ARTICLE VII – FEES AND EXPENSES

Section 701. General

- a. The developer shall be required to submit a subdivision/land development or building permit application prior to any stormwater management facilities construction. The fee for plan reviews, permit issuance, and inspections shall be established by resolution of the Municipality to defray the following expenses:
 1. The review of the stormwater management/erosion and sedimentation control plan by the Municipal Engineer.
 2. The site inspections.
 3. The inspection of stormwater management facilities and drainage improvements during construction.
 4. The final inspection upon completion of the stormwater management facilities and drainage improvements presented in the stormwater management/erosion and sedimentation control plan.
 5. Any additional work required to enforce any permit provisions regulated by this Ordinance, correct violations, and assure proper completion of stipulated remedial actions.
- b. All fees shall be paid by the Applicant at the time of application and shall be included in the required deposit for review of subdivision/land development plans.
- c. Any additional costs incurred by the Municipality in the administration of this Ordinance shall be charged to the Applicant and shall be paid promptly by the Applicant. Upon completion of the construction of the stormwater management facility and upon final approval thereof by the Municipal, any monies in excess of Municipal costs or expenses deposited by the Applicant shall be refunded to the Applicant.

ARTICLE VIII – PROHIBITIONS

Section 801. Ultimate Responsibility

The standards set forth herein and promulgated by this Section are minimum standards; therefore, this Section does not intend nor imply that compliance by any person will ensure that there will be no contamination, pollution, or unauthorized discharge of pollutants.

Section 802. Prohibited Discharges and Connections

- A. Any drain or conveyance, whether on the surface or subsurface, that allows any non-stormwater discharge including sewage, process wastewater, and wash water to enter a regulated small MS4 or to enter the surface waters of this Commonwealth is prohibited.
- B. No person shall allow, or cause to allow, discharges into a regulated small MS4, or discharges into waters of this Commonwealth, which are not composed entirely of stormwater, except (1) as provided in paragraph C below and (2) discharges authorized under a state or federal permit.
- C. The following discharges are authorized unless they are determined to be significant contributors to pollution a regulated small MS4 or to the waters of this Commonwealth:
 - 1. Discharges or flows from firefighting activities.
 - 2. Discharges from potable water sources, including water line flushing and fire hydrant flushing, if such discharges do not contain detectable concentrations of Total Residual Chlorine (TRC).
 - 3. Non-contaminated irrigation water, water from lawn maintenance, landscape drainage and flows from riparian habitats and wetlands.
 - 4. Diverted stream flows and springs.
 - 5. Non-contaminated pumped ground water and water from Foundation and footing drains and crawl space pumps.
 - 6. Non-contaminated HVAC condensation and water from geothermal systems.
 - 7. Residential (i.e., not commercial) vehicle wash water where cleaning agents are not utilized.
 - 8. Non-contaminated hydrostatic test water discharges if such discharges do not contain detectable concentrations of TRC.
- D. In the event that the Municipality or DEP determines that any of the discharges identified in Subsection C significantly contribute pollutants to a regulated small MS4 or to the waters of this Commonwealth, the Municipality or DEP will notify the responsible person(s) to cease the discharge.

Section 803. Roof Drains and Sump Pumps

Roof drains and sump pumps shall discharge to infiltration or vegetative BMPs wherever feasible.

Section 804. Alteration of SWM BMPs

No person shall modify, remove, fill, landscape, or alter any SWM BMPs, facilities, areas, or structures that were installed as a requirement of this Ordinance without the written approval of the Municipality.

Section 805. Suspension of MS4 Access

- A. *Suspension Due to Illicit Discharges in Emergency Situations.* The Municipality may, without prior notice, suspend MS4 discharge access to a person when such suspension is necessary to stop an actual or threatened discharge which presents or may present imminent and substantial danger to the environment, or to the health or welfare of persons, or to the MS4 or waters of this Commonwealth. If the violator fails to comply with a suspension order issued in an emergency, the Municipality may take such steps as deemed necessary to prevent or minimize damage to the MS4 or waters this Commonwealth, or to minimize danger to persons including, without limitation, entering onto property for the purpose of disconnecting and/or performing emergency maintenance or repairs to storm sewers. In the event the Municipality must disconnect or perform emergency maintenance and/or repairs, the Municipality may file and attach a municipal lien on the property, which is causing the illicit discharge.
- B. *Suspension Due to the Detection of Illicit Discharge or Illicit Connection.* Any person discharging to the MS4 in violation of this Section may have their MS4 access terminated if such termination would abate or reduce an illicit discharge or illicit connection. The Municipality will notify a violator of the proposed termination of its MS4 access. The violator may petition the Municipality for a reconsideration and hearing.
- C. A person commits an offense if the person reinstates MS4 access to premises terminated pursuant to this Section, without the prior approval of the Municipality.

Section 806. Industrial or Construction Activity Discharges

Any person subject to an industrial or construction activity NPDES stormwater discharge permit shall comply with all provisions of such permit. Proof of compliance with said permit shall be required in a form acceptable to the Municipality prior to the allowing of discharges to the MS4.

Section 807. Monitoring of Discharges

- A. *Applicability.* This Section applies to all facilities that have stormwater discharges associated with industrial activity, including construction activity.
- B. *Access to Facilities.*
 - 1. The Municipality shall be permitted to enter and inspect facilities subject to regulation under this Section as often as may be necessary to determine compliance with this Section. If a discharger has security measures in force that require proper identification and clearance before entry into its premises, the discharger shall make the necessary arrangements to allow access to representatives of the Municipality.
 - 2. Facility operators shall allow the Municipality ready access to all parts of the premises for the purposes of inspection, sampling, examination, and copying of records that must be kept under the conditions of an NPDES permit to discharge stormwater, and the performance of any additional duties as defined by State and Federal law.
 - 3. The Municipality shall have the right to set up on any permitted facility such devices as are necessary for the opinion of the authorized enforcement agency to conduct monitoring and/or sampling of the facility's stormwater discharge.

4. The Municipality has the right to require the discharger to install monitoring equipment as necessary. The facility's sampling and monitoring equipment shall be maintained at all times in a safe and proper operating condition by the discharger at its own expense. All devices used to measure stormwater flow, and quality shall be calibrated to ensure their accuracy.
5. Any temporary or permanent obstruction to safe and easy access to the facility to be inspected and/or sampled shall be promptly removed by the operator at the written or oral request of Municipality and shall not be replaced. The costs of clearing such access shall be borne by the operator.
6. Unreasonable delays in allowing Municipality access to a permitted facility is a violation of a stormwater discharge permit and of this Section. A person who is the operator of a facility with a NPDES permit to discharge stormwater associated with industrial activity commits an offense if the person denies the Municipality reasonable access to the permitted facility for the purpose of conducting any activity authorized or required by this Section.
7. If the Municipality has been refused access to any part of the premises from which stormwater is discharged, and it is able to demonstrate probable cause to believe that there may be a violation of this Section or that there is a need to inspect and/or sample as part of a routine inspection and sampling program designed to verify compliance with this Section or any order issued hereunder or to protect the overall public health, safety, and welfare of the community, then the Municipality may seek issuance of a search warrant from any court of competent jurisdiction.

Section 808. Requirements to Prevent, Control, & Reduce Stormwater Pollutants by the Use of BMPs

The Municipality will adopt requirements identifying best management practices for any activity, operation, or facility which may cause or contribute to pollution or contamination of stormwater, the storm drain system, or waters of this Commonwealth. The owner or operator of a commercial or industrial establishment shall provide, at their own expense, reasonable protection from accidental discharge of prohibited materials or other wastes into the municipal storm drain system or watercourses through the use of these structural and non-structural BMPs. Further, any person responsible for a property or premises, which is, or may be the source of an illicit discharge, may be required to implement, at said person's expense, additional structural and nonstructural BMPs to prevent the further discharge of pollutants to the municipal separate storm sewer system. Compliance with all terms and conditions of a valid NPDES permit authorizing the discharge of stormwater associated with industrial activity, to the extent practicable, shall be deemed compliance with the provisions of this Section. These BMPs shall be part of a stormwater pollution prevention plan (SWPP) as necessary for compliance with requirements of the NPDES permit.

Section 809. Watercourse Protection

- A. Every person owning property through which a watercourse passes, or such person's lessee, shall keep and maintain that part of the watercourse within the property free of trash, debris, excessive vegetation, and other obstacles that would pollute, contaminate, or significantly retard the flow of water through the watercourse.
- B. In addition, the owner or lessee shall maintain existing privately owned structures within or adjacent to a watercourse so that such structures will not become a hazard to the use, function, or physical integrity of the watercourse.

Section 810. Notification of Spills

Notwithstanding other requirements of law, as soon as any person responsible for a facility or operation or responsible for emergency response for a facility or operation has information of any known or suspected release of materials which are resulting or may result in illicit discharges or pollutants discharging into stormwater, the storm drain system, or water of this Commonwealth said person shall take all necessary steps to ensure the discovery, containment, and cleanup of such release. In the event of such a release of hazardous materials, said person shall immediately notify emergency response agencies of the occurrence via emergency dispatch services. In the event of a release of non-hazardous materials, said person shall notify the Municipality in person or by phone or facsimile no later than the next business day. Notifications in person or by phone shall be confirmed by written notice addressed and mailed to the Municipality within 3 business days of the phone notice. If the discharge of prohibited materials emanates from a commercial or industrial establishment, the owner or operator of such establishment shall also retain an on-site written record of the discharge and the actions taken to prevent its recurrence. Such records shall be retained for at least three (3) years.

ARTICLE IX – ENFORCEMENT AND PENALTIES

Section 901. Enforcement

- A. It shall be the responsibility of the Owner of the real property on which any Regulated Activity is proposed to occur, is occurring, or has occurred, to comply with the terms and conditions of this Ordinance.
- B. It shall be unlawful for a person to undertake any Regulated Activity except as provided in an approved SWM Site Plan, unless specifically exempted in this Ordinance.
- C. It shall be unlawful to violate any Section of this Ordinance.
- D. Inspections regarding compliance with the SWM Site Plan are the responsibility of the Municipality.
- E. Notice of Violation.

When a person has violated a prohibition of this Ordinance, otherwise fails to comply with the requirements of this Ordinance, or fails to conform to the requirements of any permit issued hereunder, the Municipality shall provide written notification of the violation to the property Owner. Such notification shall set forth the nature of the violations and establish a time limit for the correction of these violation(s). Failure to comply or remediate and/or restore within the established deadline shall be cause for the work will be done by a designated governmental agency or a contractor, and the expense thereof shall be charged to the violator or assessed as a municipal lien on the property.

Such written notice may require, without limitation:

1. The performance of monitoring, analyses, and reporting.
2. The elimination of illicit connections or illicit discharges.
3. That violating discharges, practices, or operations shall cease and desist.
4. The abatement or remediation of stormwater pollution or contamination hazards and the restoration of any affected property.
5. Payment of a fine to cover administrative and remediation costs.
6. The implementation of source control or treatment BMPs.

Section 902. Appeals of Notice of Violation

- A. Any person receiving a notice of violation may appeal the determination of the Municipality. The notice of appeal must be received within 30 days from the date of the notice of violation. Hearing on the appeal before a designated hearing representative of the Municipality shall take place within 15 days from the date of receipt of the notice of appeal.
- B. Any person aggrieved by any action of the Municipality or its designee, relevant to the provisions of this Ordinance, may appeal to the Municipality within 30 days of that action.
- C. Any person aggrieved by any decision of the Municipality, relevant to the provisions of this Ordinance, may appeal to the County Court of Common Pleas in the county where the activity has taken place within 30 days of the Municipality's decision.

Section 903. Enforcement Measures after Appeal

If the violation has not been corrected pursuant to the requirements set forth in the notice of violation, or, in the event of an appeal, within 15 days of the hearing representative's decision upholding the decision of the Municipality, then representatives of the Municipality shall enter upon the subject private property and are authorized to take any and all measures necessary to abate the violation and/or restore the property. It shall be unlawful for any person, Owner, agent, or person in possession of any premises to refuse to allow the Municipality or designated contractor to enter upon the premises for the purposes set forth above.

Section 904. Cost of Abatement of Violation

- A. Within 30 days after abatement of the violation, the Owner of the property will be notified of the cost of abatement, including administrative costs. The property Owner may thereafter file a written protest objecting to the amount of the assessment within 30 days. If the amount due is not paid within a timely manner as determined by the decision of the Municipality or by the expiration of the time in which to file an appeal, the charges shall become a special assessment against the property and shall constitute a municipal lien on the property for the amount of the assessment.
- B. Any person violating any of the provisions of Article VIII of this Ordinance shall become liable to the Municipality by reason of such violation. The liability shall be paid in not more than 12 equal payments. Interest at the rate of 12 percent per annum shall be assessed on the balance beginning on the first day following discovery of the violation.

Section 905. Injunctive Relief

It shall be unlawful for any person to violate any provision or fail to comply with any of the requirements of this Ordinance. If a person has violated or continues to violate the provisions of this Ordinance, the Municipality may petition for a preliminary or permanent injunction restraining the person from activities that would create further violations or compelling the person to perform abatement or remediation of the violation.

Section 906. Compensatory Action

In lieu of enforcement proceedings, penalties, and remedies authorized by this Ordinance, the authorized enforcement agency may impose upon a violator alternative compensatory actions, such as storm drain stenciling, attendance at compliance workshops, creek cleanup, etc.

Section 907. Violations Deemed as Public Nuisance

In addition to the enforcement processes and penalties provided, any condition caused or permitted to exist in violation of any of the provisions of this Ordinance is a threat to public health, safety, and welfare, and is declared and deemed a public nuisance, and may be summarily abated or restored at the violator's expense, and/or a civil action to abate, enjoin, or otherwise compel the cessation of such public nuisance may be taken.

Section 908. Criminal Prosecution and Penalties

- A. Any person that has violated or continues to violate this Ordinance shall be liable to criminal prosecution to the fullest extent of the law, and shall be subject to a criminal penalty of up to \$1,000.00 per violation per day.
- B. Anyone violating the provisions of this Ordinance shall be guilty of a summary offense, and upon conviction, shall be subject to a fine of not more than \$1,000.00 for each violation, recoverable with costs and/or imprisonment for a period of time not to exceed 90 days.

- C. Each day that the violation continues shall be a separate offense, and penalties shall be cumulative.
- D. In addition, the Municipality may institute injunctive, mandamus, or any other appropriate action or proceeding at law or in equity for the enforcement of this Ordinance. Any court of competent jurisdiction shall have the right to issue restraining orders, temporary or permanent injunctions, mandamus, or other appropriate forms of remedy or relief.
- E. All such penalties shall be deemed cumulative and do not prevent the Municipality from pursuing any and all remedies.

Section 909. Attorney Fees and Costs

The Municipality may recover all attorney fees, court costs, and other expenses associated with enforcement of this Ordinance, either criminal or civil, including sampling and monitoring expenses or other costs of investigation.

Section 910. Remedies Not Exclusive

The remedies listed in this Ordinance are not exclusive of any other remedies available under any applicable Federal, State, or local law, and it is within the discretion of the Municipality to seek cumulative remedies.

Section 911. Right-of-Entry

Upon presentation of proper credentials, the Municipality or its designated agent may enter at reasonable times upon any property within the Municipality to inspect the condition of the stormwater structures and facilities in regard to any aspect regulated by this Ordinance.

Section 912. Inspection

- A. The landowner or the owner's designee (including the Municipality for dedicated and owned facilities) shall inspect SWM BMPs, facilities and/or structures installed under this Ordinance according to the following frequencies, at a minimum, to ensure the BMPs, facilities and/or structures continue to function as intended:
 - 1. Annually for the first five (5) years.
 - 2. Once every three (3) years thereafter.
 - 3. During or immediately after the cessation of a 10-year or greater storm.
 - 4. All stormwater BMPs serving non-residential development or serving more than one residential unit shall be inspected, and a report of such inspection shall be submitted to the Municipality for review on an annual basis.
 - 5. All inspection records shall be maintained by the landowner and shall be made available to the Municipality upon written request.
- B. Inspections should be conducted during or immediately following precipitation events. A written inspection report shall be created to document each inspection. The inspection report shall contain the date and time of the inspection, the individual(s) who completed the inspection, the location of the BMP, facility or structure inspected, observations on performance, and recommendations for improving performance, if applicable. Inspection reports shall be submitted to the Municipality within 30 days following completion of the inspection.

Section 913. Notifications

In the event that a person fails to comply with the requirements of this Ordinance, or fails to conform to the requirements of any permit issued hereunder, the Municipality shall provide written notification of the violation. Such notification shall set forth the nature of the violations and establish a time limit for the correction of these violation(s). Failure to comply within the time specified shall subject such person to the penalty provisions of this Ordinance. All such penalties shall be deemed cumulative and do not prevent the Municipality from pursuing any and all remedies. It shall be the responsibility of the owner of the real property on which any Regulated Activity is proposed to occur, is occurring, or has occurred, to comply with the terms and conditions of this Ordinance.

Section 914. Enforcement

- A. It shall be unlawful for a person to undertake any Regulated Activity except as provided in an approved SWM Site Plan, unless specifically exempted in Section 302.
- B. It shall be unlawful to violate Section 803 of this Ordinance.
- C. Inspections regarding compliance with the SWM Site Plan are the responsibility of the Municipality.

Section 915. Suspension and Revocation

- A. Any approval or permit issued by the Municipality pursuant to this Ordinance may be suspended or revoked for:
 - 1. Non-compliance with or failure to implement any provision of the approved SWM Site Plan or O&M Agreement.
 - 2. A violation of any provision of this Ordinance or any other applicable law, ordinance, rule, or regulation relating to the Regulated Activity.
 - 3. creation of any condition or the commission of any act during the Regulated Activity which constitutes or creates a hazard, nuisance, pollution, or endangers the life or property of others.
- B. A suspended approval may be reinstated by the Municipality when:
 - 1. The Municipality has inspected and approved the corrections to the violations that caused the suspension.
 - 2. The Municipality is satisfied that the violation has been corrected.
- C. An approval that has been revoked by the Municipality cannot be reinstated. The Applicant may apply for a new approval under the provisions of this Ordinance.
- D. If a violation causes no immediate danger to life, public health, or property, at its sole discretion, the Municipality may provide a limited time period for the owner to correct the violation. In these cases, the Municipality will provide the owner, or the owner's designee, with a written notice of the violation and the time period allowed for the owner to correct the violation. If the owner does not correct the violation within the allowed time period, the Municipality may revoke or suspend any or all applicable approvals and permits pertaining to any provision of this Ordinance.

Section 916. Penalties

- A. Anyone violating the provisions of this Ordinance shall be guilty of a summary offense, and upon conviction, shall be subject to a fine of not more than \$1000.00 for each violation, recoverable with costs. Each day that the violation continues shall be a separate offense, and penalties shall be cumulative.
- B. In addition, the Municipality may institute injunctive, mandamus, or any other appropriate action or proceeding at law or in equity for the enforcement of this Ordinance. Any court of competent jurisdiction shall have the right to issue restraining orders, temporary or permanent injunctions, mandamus, or other appropriate forms of remedy or relief.

Section 917. Appeals

- A. Any person aggrieved by any action of the Municipality or its designee, relevant to the provisions of this Ordinance, may appeal to the Municipality within 30 days of that action.
- B. Any person aggrieved by any decision of the Municipality, relevant to the provisions of this Ordinance, may appeal to the County Court of Common Pleas in the county where the activity has taken place within 30 days of the Municipality's decision.

Hamilton Township Stormwater Management Ordinance

(Ordinance Number)


ENACTED and **ORDAINED** at a regular meeting of the

HAMILTON TOWNSHIP BOARD OF SUPERVISORS

on this 4th day of December, 2023


This Ordinance shall take effect immediately.


ATTEST:



Name/Title:

(SEAL)

HAMILTON TOWNSHIP:


Name/Title: Chairman


Name/Title: vice Chairman


Name/Title: Supervisor

ARTICLE X – REFERENCES

Section 1001. References

1. U.S. Department of Agriculture, National Resources Conservation Service (NRCS). *National Engineering Handbook*. Part 630: Hydrology, 1969-2001. Originally published as the *National Engineering Handbook*, Section 4: Hydrology. Available from the NRCS online at: <http://www.nrcs.usda.gov/>.
2. U.S. Department of Agriculture, Natural Resources Conservation Service. 1986. *Technical Release 55: Urban Hydrology for Small Watersheds*, 2nd Edition. Washington, D.C.
3. Pennsylvania Department of Environmental Protection. No. 363-2134-008 (March 31, 2012), as amended and updated. *Erosion and Sediment Pollution Control Program Manual (E&S Manual³)*. Harrisburg, PA.
4. Pennsylvania Department of Environmental Protection. No. 363-0300-002 (December 2006), as amended and updated. *Pennsylvania Stormwater Best Management Practices Manual*. Harrisburg, PA.
5. U.S. Department of Commerce, National Oceanic and Atmospheric Administration, National Weather Service, Hydrometeorological Design Studies Center. 2004-2006. *Precipitation-Frequency Atlas of the United States, Atlas 14, Volume 2, Version 3.0*, Silver Spring, Maryland. Internet address: <http://hdsc.nws.noaa.gov/hdsc/pfds/>.

TABLES

TABLE 1**Runoff Curve Numbers**
[From NRCS (SCS) TR-55]

LAND USE DESCRIPTION		HYDROLOGICAL SOIL GROUP							
		A	B	C	D				
Open Space		44	65	77	82				
Meadow		30**	58	71	78				
Agricultural		59	71	79	83				
Forest		36**	60	73	79				
Commercial (85% Impervious)		89	92	94	95				
Industrial (72% Impervious)		81	88	91	93				
Institutional (50% Impervious)		71	82	88	90				
Residential									
<u>Average Lot Size</u>	<u>% Impervious</u>								
1/8 Acre or less	*65					77	85	90	92
1/8 – 1/3 Acre	34					59	74	82	87
1/3 – 1 Acre	23					53	69	90	85
1 – 4 Acre	12	46	66	78	80				
Farmstead		59	74	82	83				
Smooth Surfaces <i>(Concrete, Asphalt, Gravel or Bare Compacted Soil)</i>		98	98	98	98				
Water		98	98	98	98				
Mining Newly Graded Areas <i>(Pervious Areas Only)</i>		77	86	91	94				

*Includes Multi-Family Housing unless justified lower density can be provided.

**Caution - CN values under 40 may produce erroneous modeling results.

NOTE: Site conditions of bare earth or fallow shall be considered as meadow when choosing a CN value for existing undeveloped conditions.

NOTE: CN values consistent with the June 1986 release of the TR-55 (Urban Hydrology for Small Watersheds) may be utilized for consistency with PADEP Worksheets.

TABLE 2
RATIONAL RUNOFF COEFFICIENTS
By Hydrologic Soils Group and Overland Slope (%)

Land Use	A			B			C			D		
	0-2%	2-6%	6%+	0-2%	2-6%	6%+	0-2%	2-6%	6%+	0-2%	2-6%	6%+
Cultivated Land	0.08	0.13	0.16	0.11	0.15	0.21	0.14	0.19	0.26	0.18	0.23	0.31
	0.14	0.18	0.22	0.16	0.21	0.28	0.20	0.25	0.34	0.24	0.29	0.41
Pasture	0.12	0.20	0.30	0.18	0.28	0.37	0.24	0.34	0.44	0.30	0.40	0.50
	0.15	0.25	0.37	0.23	0.34	0.45	0.30	0.42	0.52	0.37	0.50	0.62
Meadow	0.10	0.16	0.25	0.14	0.22	0.30	0.20	0.28	0.30	0.24	0.30	0.40
	0.14	0.22	0.30	0.20	0.28	0.37	0.26	0.35	0.44	0.20	0.40	0.50
Forest	0.05	0.08	0.11	0.08	0.11	0.14	0.10	0.13	0.16	0.12	0.16	0.20
	0.08	0.11	0.14	0.10	0.14	0.18	0.12	0.16	0.20	0.15	0.20	0.25
Residential												
Lot Size 1/8 Acre	0.25	0.28	0.31	0.27	0.30	0.25	0.30	0.33	0.38	0.33	0.36	0.42
	0.33	0.37	0.40	0.35	0.39	0.44	0.38	0.42	0.49	0.41	0.43	0.34
Lot Size 1/4 Acre	0.22	0.26	0.29	0.24	0.29	0.33	0.27	0.31	0.36	0.30	0.34	0.40
	0.30	0.34	0.37	0.33	0.37	0.42	0.36	0.40	0.47	0.38	0.42	0.52
Lot Size 1/3 Acre	0.19	0.23	0.26	0.22	0.26	0.30	0.25	0.29	0.34	0.28	0.32	0.39
	0.28	0.32	0.35	0.30	0.35	0.39	0.33	0.38	0.45	0.36	0.40	0.50
Lot Size 1/2 Acre	0.16	0.20	0.24	0.19	0.23	0.28	0.22	0.27	0.32	0.26	0.30	0.37
	0.25	0.29	0.32	0.28	0.32	0.36	0.31	0.35	0.42	0.34	0.38	0.48
Lot Size 1 Acre	0.14	0.19	0.22	0.17	0.21	0.26	0.20	0.25	0.31	0.24	0.29	0.31
	0.22	0.26	0.29	0.24	0.28	0.34	0.28	0.32	0.40	0.21	0.35	0.46
Industrial	0.67	0.68	0.68	0.68	0.68	0.69	0.68	0.69	0.69	0.69	0.69	0.70
	0.85	0.85	0.86	0.85	0.86	0.86	0.86	0.86	0.87	0.86	0.86	0.88
Commercial	0.71	0.71	0.72	0.71	0.72	0.72	0.72	0.72	0.72	0.72	0.72	0.72
	0.88	0.88	0.89	0.80	0.82	0.84	0.84	0.85	0.89	0.89	0.91	0.95
Streets	0.70	0.71	0.71	0.71	0.72	0.74	0.72	0.73	0.76	0.73	0.75	0.78
	0.76	0.77	0.79	0.80	0.82	0.84	0.84	0.85	0.89	0.89	0.91	0.95
Open Space	0.03	0.10	0.14	0.08	0.10	0.19	0.12	0.17	0.24	0.16	0.21	0.28
	0.11	0.16	0.20	0.14	0.19	0.26	0.18	0.23	0.32	0.22	0.27	0.39
Parking	0.85	0.85	0.87	0.85	0.86	0.87	0.85	0.86	0.87	0.85	0.86	0.87
	0.95	0.96	0.97	0.95	0.96	0.97	0.95	0.96	0.97	0.95	0.96	0.97

Runoff coefficient is for storm recurrence intervals less than 25 years.

Runoff coefficients for storm recurrence intervals 25 years or more.

Source: Rawls, W.J., S.L. Wong and 11.H. McCuen, 1981, "Comparison of Urban Flood Frequency Procedures", Preliminary Draft, U.S. Department of Agriculture, Soil Conservation Service, Baltimore, MD.

TABLE 3

Roughness Coefficients (Manning's "n") for Overland Flow
(U.S. Army Corps of Engineers, HEC-1 Users Manual)

<u>Surface Description</u>	<u>n</u>
Dense Growth	0.4 – 0.5
Pasture	0.3 – 0.4
Lawns	0.2 – 0.3
Bluegrass Sod	0.2 – 0.5
Short Grass Prairie	0.1 – 0.2
Sparse Vegetation	0.05 – 0.13
Bare Clay-Loam Soil (<i>eroded</i>)	0.01 – 0.03
Concrete/Asphalt –	
very shallow depths (<i>less than 1/4 inch</i>)	0.10 – 0.15
small depths (<i>1/4 inch to several inches</i>)	0.05 – 0.10

Roughness Coefficients (Manning's "n") for Sheet Flow
(U.S. Conservation Service Technical Release 55)

<u>Surface Description</u>	<u>n</u>
Smooth Surfaces (<i>concrete, asphalt, gravel, or bare soil</i>)	0.011
Fallow (<i>no residue</i>)	0.05
Cultivated Soils:	
Residue Cover Less Than 20%	0.06
Residue Cover Greater Than 20%	0.17
Grass:	
Short Prairie Grass	0.15
Dense Grasses	0.24
Bermuda Grass	0.41
Range (<i>natural</i>)	0.13
Woods:	
Light Underbrush	0.40
Dense Underbrush	0.80

APPENDIX A

OPERATION AND MAINTENANCE (O&M) AGREEMENT

STORMWATER MANAGEMENT BEST MANAGEMENT PRACTICES (SWM BMPs)

OPERATION AND MAINTENANCE (O&M) AGREEMENT
STORMWATER MANAGEMENT BEST MANAGEMENT PRACTICES (SWM BMPs)

THIS AGREEMENT, made and entered into this _____ day of _____, 20____, by and between _____ (hereinafter the "Landowner"), and **HAMILTON TOWNSHIP**, Adams County, Pennsylvania (hereinafter "Municipality");

WITNESSETH

WHEREAS, the Landowner is the owner of certain real property located at _____, Hamilton Township, Adams County, PA, as recorded by deed in the land records of Adams County, Pennsylvania, Deed Book _____ at Page _____, (hereinafter "Property").

WHEREAS, the Landowner is proceeding to build and develop the Property; and

WHEREAS, the _____ (*Insert Plan Title such as: SWM Site Plan, Post Construction Stormwater Management Plan, Land Development Plan, Operation and Maintenance (O&M) Plan*) approved by the Municipality (hereinafter referred to as the "Plan") for the property identified herein, which is attached hereto as Appendix A and made part hereof, as approved by the Municipality, provides for management of stormwater within the confines of the Property through the use of BMPs; and

WHEREAS, the Municipality, and the Landowner, his successors and assigns, agree that the health, safety, and welfare of the residents of the Municipality and the protection and maintenance of water quality require that on-site SWM BMPs be constructed and maintained on the Property; and

WHEREAS, the Municipality requires, through the implementation of the Plan, that SWM BMPs as required by said Plan and the Municipal Stormwater Management Ordinance be constructed and adequately operated and maintained by the Landowner, successors, and assigns.

NOW, THEREFORE, in consideration of the foregoing promises, the mutual covenants contained herein, and the following terms and conditions, the parties hereto agree as follows:

1. The Landowner shall construct the BMPs in accordance with the plans and specifications identified in the Plan.
2. The Landowner shall operate and maintain the BMPs as shown on the Plan in good working order in accordance with the specific operation and maintenance requirements noted on the approved Plan.
3. The Landowner hereby grants permission to the Municipality, its authorized agents and employees, to enter upon the property, at reasonable times and upon presentation of proper credentials, to inspect the BMPs whenever necessary. Whenever possible, the Municipality shall notify the Landowner prior to entering the property.
4. In the event the Landowner fails to operate and maintain the BMPs per paragraph 2, the Municipality or its representatives may enter upon the Property and take whatever action is deemed necessary to maintain said BMP(s). It is expressly understood and agreed that the Municipality is under no obligation to maintain or repair said facilities, and in no event shall this Agreement be construed to impose any such obligation on the Municipality.

5. In the event the Municipality, pursuant to this Agreement, performs work of any nature, or expends any funds in performance of said work for labor, use of equipment, supplies, materials, and the like, the Landowner shall reimburse the Municipality for all expenses (direct and indirect) incurred within 10 days of receipt of invoice from the Municipality.
6. The intent and purpose of this Agreement is to ensure the proper maintenance of the on-site BMPs by the Landowner; provided, however, that this Agreement shall not be deemed to create any additional liability of any party for damage alleged to result from or be caused by stormwater runoff.
7. The Landowner, its executors, administrators, assigns, and other successors in interests, shall release the Municipality from all damages, accidents, casualties, occurrences, or claims which might arise or be asserted against said employees and representatives from the construction, presence, existence, or maintenance of the BMP(s) by the Landowner or Municipality.
8. The Municipality intends to inspect the BMPs at a minimum of once every three (3) years to ensure their continued functioning.

This Agreement shall be recorded at the Office of the Recorder of Deeds of Adams County, Pennsylvania, and shall constitute a covenant running with the Property and/or equitable servitude, and shall be binding on the Landowner, his administrators, executors, assigns, heirs, and any other successors in interests, in perpetuity.

IN WITNESS WHEREOF, the parties have executed this Agreement on the day and year first above written.

ATTEST:

LANDOWNER:

By: _____
 Name/Title

By: _____
 Name/Title

ATTEST:

 Name/Title

MUNICIPALITY:

Hamilton Township

By: _____
 Name/Title

(SEAL)

COMMONWEALTH OF PENNSYLVANIA

: ss

COUNTY OF _____

On this, the ____ day of _____, 20____, before me, the undersigned officer, personally appeared _____, who acknowledged [himself] [herself] [themselves] to be the _____ of _____ and that [he] [she] [they] executed the within Agreement on behalf of _____ by signing [his] [her] [their] name as such _____.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

(SEAL)

My commission expires:

COMMONWEALTH OF PENNSYLVANIA

: ss

COUNTY OF _____

On this, the ____ day of _____, 20____, before me, the undersigned officer, personally appeared _____, who acknowledged [himself] [herself] to be the _____ of HAMILTON TOWNSHIP and that [he] [she] executed the within Agreement on behalf of HAMILTON TOWNSHIP by signing [his] [her] name as such, _____.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

(SEAL)

My commission expires:

Appendix B
Infiltration Testing

Infiltration Testing

Infiltration BMPs shall be designed in the following manner: A detailed soils evaluation of the project site shall be performed to determine the suitability of recharge facilities. The evaluation shall be performed by a qualified professional and, at a minimum, address soil permeability, depth to bedrock, susceptibility to sinkhole formation and subgrade stability, seasonally high groundwater table, suitability of stormwater management facilities, and maximum infiltration capacity in depth of water per unit area. The general process for designing the infiltration BMP shall be:

- A. Site evaluation to determine general areas of suitability for infiltration practices.
- B. Infiltration tests must be taken at the location and elevation of the facility's bottom for each proposed practice. At least two separate tests shall be taken at the location of each SWM facility.
- C. A double-ring infiltrometer test shall be used for all infiltration tests in accordance with the current edition of the BMP Manual.
- D. Upon completion of site evaluation and infiltration tests, the design infiltration rate shall be determined from the tested infiltration rates by using the geometric mean. The geometric mean, not the arithmetic mean, of the multiple infiltration tests, must be reported and used. In some situations, a measured rate of zero may be obtained. In these cases, a default value should be used based on one decimal digit less than the smallest detectable reading for that particular test. For example, if the smallest detectable reading using an infiltrometer is a 0.15 inch drop, then 0.14 inches should be substituted for the zero reading. The geometric mean of a data set is the nth root of the product of "n" numbers:

$$\sqrt[n]{x_1 * x_2 * x_3 \dots x_n}$$

- E. The infiltration requirement in the high-quality/exceptional waters shall be subject to Title 25, Chapter 93, of the Pennsylvania Code of Regulations and the antidegradation regulations promulgated by DEP thereunder.

Appendix C

Small Project Approach

STORMWATER MANAGEMENT

SMALL PROJECT APPROACH

For Small Projects in
Hamilton Township, Adams County, Pennsylvania

TABLE OF CONTENTS

I.	Directions and Review Process.....	Page C2
II.	Application and Permit	Page C3
III.	Record of Proposed Impervious	Page C4
IV.	Minor Stormwater Management Plan Requirements	Page C5
V.	How to Determine Disconnected Impervious Area (DIA)	Page C6
VI.	Chart for Determining BMPs Based on Volume Required	Page C7
VII.	Stormwater Management/ BMP Facilities Operation & Maintenance Agreement	Page C9
VIII.	Standard Details	Page C12

Introduction:

This Small Project Approach has been created as a tool to help property owners manage stormwater on their property and streamline the process of designing on-site stormwater management facilities for new, relatively minor residential and accessory structure projects. Through the use of this manual, residents have the ability to determine the appropriate facilities for their property, project, and budget. This approach is consistent with the Simplified Approach in the Adams County Act 167 Stormwater Management Plan. This design method is not intended to be used with large-scale subdivision / land development projects or activities that include infrastructure such as roadways.

I. Directions and Review Process

- A. For Small Projects with a total cumulative impervious surface area added since November 23, 2011 **less than or equal to 1,000 ft²** submit two copies of the following along with the applicable fee:
1. Completed Application and Permit Worksheet (Section II).
 2. Stormwater Management Sketch Plan as required under Section IV.A.
 3. Record of Impervious Worksheet (Section III) with completed columns 1 through 3 only.
- B. For Small Projects with a total cumulative impervious surface area added since November 23, 2011 **greater than 1,000 ft² and less than or equal to 10,000 ft²** submit two copies of the following along with the applicable fee:
1. Complete Application and Permit Worksheet (Section II).
 2. Minor Stormwater Management Plan as required under Section IV.B.
 3. Record of Impervious Worksheet (Section III) with completed columns 1 through 4 for areas that can be considered disconnected or all 7 columns for areas that cannot be considered disconnected.
 4. For all proposed impervious surfaces that cannot be completely disconnected, calculate the volume of stormwater runoff required to be captured by Stormwater BMPs. Multiply the contributory square footage of impervious draining to the BMP by 0.25 (Column 2 x 0.25 = Column 5). Using the "Chart for Determining BMP sizing" based on Volume Required (Section VI) and Standard Details (Section VIII), choose the BMP and size required for each contributory impervious area. Note that the standard details are not a comprehensive list of stormwater BMP's available. Additional information and variation is located in the *Guide to Choosing Stormwater BMPs* in Appendix C of the Adams County Act 167 Stormwater Management Plan. It is the Applicant's responsibility to select a facility and determine the appropriate size.
 5. Complete and sign the Stormwater Management/BMP Facilities Operation & Maintenance Agreement, hereinafter referred to as O&M Agreement. (Section VII).
- C. The Application shall not be considered to be complete unless it includes all of the information required. Upon receipt of a complete application, the official designated by the Municipality to administer the Small Project Approach process shall review the application against the requirements applicable to Small Project Approach submissions.
1. The designated official shall approve the application if the application conforms to applicable requirements. Upon approval of a complete application packet, the designated official shall sign the permit and issue a copy to the Applicant.
 2. The designated official shall deny the application if the application does not conform to applicable requirements. Any denial shall be in writing and shall state the reasons for such denial. The designated official shall approve or deny the complete application within fifteen (30) calendar days of the date of filing. The property owner may, in response to denied Small Project Approach submission, resubmit the application with revisions necessary to address the reasons for denial.
- D. Once the permit is signed and its receipt acknowledged, the Applicant is authorized to initiate construction of the approved project the Applicant is responsible for contacting the designated official at a minimum of 72 hours prior to start of construction to schedule inspection. Typically, up to 3 inspections could be performed during and after completion of the stormwater management facilities.

II. Application and Permit

Property Owner's Name: _____ Phone No: _____
Address of Property: _____
Address of Owner: _____
Contact Phone No. (if different than the Owner): _____
Contact Email: _____
Parcel ID #: _____
Total Existing Impervious on the Property: _____
Total Impervious on the Lot after Project: _____
New Impervious Area Associated with this Project: _____
Are there any known existing drainage problems or the potential for the proposed project to create drainage problems? (if yes please explain) _____

Declaration and Acknowledgement:

- I (we) declare that I am the Property Owner, or Representative of the Owner, and that the information provided is accurate to the best of my knowledge. I (we) agree to assume full responsibility for the implementation. I (we) understand that stormwater may not adversely affect adjacent properties or be directed onto another property without written permission. I (we) declare that the proposed project will not adversely affect any, septic systems, or drinking water wells on this or any other property.
- I (we) understand that false information may result in a stop work order or revocation of permits. Municipal representatives are granted reasonable access to the property for review and/ or inspection of this project. I (we) acknowledge that the steps, assumptions, and guidelines provided in this submission, including but not limited to the Minor Stormwater Management Plan, the Record of Proposed Impervious and the Stormwater Management / BMP Facilities and Maintenance Agreement (if applicable) will be adhered to.

Applicant Acknowledgement of Submission:

Signature: _____ Date: _____

NOTE: Development activities shall begin only after the Municipality approves the Minor Stormwater Management Plan.

Permit approved by Municipality:

Municipal Official:

Signature: _____ Date: _____

Title: _____

III. Record of Impervious

Record of Proposed Impervious							
Column 1	Column 2	Column 3	Column 4	Column 5	Column 6	Column 7	Column 8
Number (corresponding to Minor Stormwater Management Plan Proposed Impervious)	Area of Proposed Impervious (ft ²)	Description (Roof, Patio, Pavement, Driveway, Gravel, etc.)	Does the Impervious Area Meet the Requirements to be Disconnected? <i>Section V (yes/no)</i>	Contributory Area Storage Requirement; Storage (ft ³) = Area (ft ²) x .25; Column 4 x .25	BMP used to Control Required Volume (ft ³)	BMP Size Requirement from Chart for Determining BMPs Sizing Based on Volume Required- <i>Section VI</i>	Notes (minimum date)
PROPOSED IMPERVIOUS SINCE NOVEMBER 23, 2011							
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							
EXISTING IMPERVIOUS BEFORE NOVEMBER 23, 2011							
A							
B							
C							
D							
E							
F							
G							
H							
I							
J							

IV. Minor Stormwater Management Plan Requirements

The Adams County Office of Planning and Development can provide assistance to Applicants to obtain property maps with the below required items, for a small fee.

A. Sketch Plan Requirements

1. Property Boundary
2. North Arrow and Scale (graphic) of 1"=50' or less.
3. Aerial Photo (if the land use has changed from the photo then draw in the approximate land uses (grass, woods, etc.).
4. Building Setbacks (Labeled)
5. 5' Contours or smaller where appropriate for the scale of the plan (Labeled)
6. Soils (Labeled)
7. Location of all existing and proposed impervious areas such as roofs, driveways, etc. with dimensions of each. The proposed impervious areas shall be numbered (1, 2, ...) and shall correspond to the number on the Record sheet.
8. The location and direction of flow discharge from existing and proposed impervious areas shown with a flow arrow other symbol.
9. Property Owners Signature.

B. Minor Stormwater Management Plan Requirements

1. Section IV.A, Sketch Plan Requirements
2. Slope/flow direction arrows on and 100 feet beyond the property line. If the property is of substantial size, and the proposed impervious is within the lot interior, the slope/flow direction arrows shall be shown for minimum of 100 feet beyond the Regulated Activity area.
3. Distance from proposed discharge location, along the flow path, to property lines, drainage ways (natural or manmade), wooded areas, and structures. If applying for the DIA credit, label the DIA flow path and length on the plan.
4. Distance between structures and proposed stormwater facilities along with elevations of both.
5. Natural and/or manmade drainage features such as drainage ways, streams, wetlands etc. on the property and within 100 feet beyond the property line.
6. Manmade features or structures such as buildings 100 feet beyond the property line on the downstream/receiving flow site.
7. Wells and on-site septic systems on and 100 feet beyond the property line.
8. Any other pertinent information that may be significant to the project site (steep slopes, etc.).
9. Size and location of stormwater BMP's with dimensions and details (as required).
10. Soil hydrologic soil group (listed under the soil).
11. Any existing and proposed structure(s) first floor elevations.
12. Grading spot elevations and/or contours defining the proposed flow characteristics.
13. Approximate distance from house and elevation of proposed stormwater BMPs and overflow paths.

V. How to Determine a Disconnected Impervious Area (DIA)

When impervious surface areas like rooftops and paved areas are directed to a pervious area that allows for infiltration, filtration, and increased time of concentration, the impervious surface areas may qualify to be treated as Disconnected Impervious Area (DIAs).

Impervious Area is defined in the definitions section of the ordinance.

A. **Rooftop Disconnection:** Impervious is considered to be disconnected if it meets the requirements listed below:

1. The contributing impervious drainage area to each disconnected discharge (downspout) is less than 500 SF.
2. The overland flow path from runoff discharge point has a slope of five percent (5%) or less.
3. Soils along the overland flow path are not classified as hydrologic group "D"
4. The overland flow path is maintained as at least 90% uniformly vegetated condition.
5. The receiving pervious area shall not include another person's property unless written permission has been obtained from the affected property owner.
6. The length of flow path must be 75 feet in length.
7. The distance between discharge points and flow paths must be and remain a minimum of 8 feet apart for entire 75 feet.

B. **Paved Disconnection:** Paved surfaces can be considered disconnected if they, or the adjacent areas, meet the following requirements:

1. The contributing flow path over the impervious area is not more than 75 feet.
2. The length of the overland flow is greater than or equal to the maximum length of flow over the impervious area.
3. The slope of both the contributing impervious area and the overland flow path is five percent (5%) or less.
4. If discharge is concentrated at one or more discrete points, no more than 500 ft² may discharge to any one point. In addition, a gravel strip or other spreading device is required for concentrated discharges. For non-concentrated discharges along the entire edge of paved surface, a level spreader is not required; however, there must be provisions for the establishment of vegetation along the paved edge.

VI. Chart for Determining BMP Sizing

BMP							
	Rain Garden/ BioRetention	Infiltration Trench	Infiltration Bed	Infiltration Berm	PA Native Deciduous Tree*	PA Native Evergreen Tree*	Rain Barrel (55 Gal Typ)
Variable Determining Size							
Volume Required (ft ³)	Area (ft ²)	Length (ft)	Area (ft ²)	Length (ft)	Quantity (ea)	Quantity (ea)	Quantity (ea)
12.5	4	8	21	3	2	1	2
25	14	16	42	6	4	3	3
50	36	31	83	11	8	5	7
75	59	47	125	17	13	8	10
100	82	63	167	22	17	10	14
125	106	78	208	28	21	13	17
150	130	94	250	33	25	15	20
175	154	109	292	39	29	18	
200	178	125	333	44	33	20	
225	203	141	375	50	38	23	
250	227	156	417	56	42	25	
275	252	172	458	61	46	28	
300	277	188	500	67	50	30	
325	302	203	542	72			
350	326	219	583	78			
375	351	234	625	83			
400	376	250	667	89			
425	401	266	708	94			
450	426	281	750	100			
475	451	297	792	106			
500	476	313	833	111			
525	502	328	875	117			
550	527	344	917	122			
575	552	359	958	128			
600	577	375	1000	133			
625	602	391	1042	139			
650	628	406	1083	144			
675	653	422	1125	150			
700	678	438	1167	156			
725	704	453	1208	161			
750	729	469	1250	167			
775	754	484	1292	172			
800	780	500	1333	178			
825	805	516	1375	183			
850	830	531	1417	189			
875	856	547	1458	194			
900	881	563	1500	200			
925	907	578	1542	206			
950	932	594	1583	211			
975	958	609	1625	217			
1000	983	625	1667	222			
1025	1008	641	1750	239			
1050	1034	656	1750	233			
1075	1059	672	1792	239			
1100	1085	688	1833	244			
1125	1110	703	1875	250			
1150	1136	719	1917	256			
1175	1162	734	1958	261			
1200	1187	750	2000	267			
1225	1213	766	2042	272			
1250	1238	781	2083	278			

BMP							
	Rain Garden/ BioRetention	Infiltration Trench	Infiltration Bed	Infiltration Berm	PA Native Deciduous Tree*	PA Native Evergreen Tree*	Rain Barrel (55 Gal Typ)
Variable Determining Size							
Volume Required (ft³)	Area (ft²)	Length (ft)	Area (ft²)	Length (ft)	Quantity (ea)	Quantity (ea)	Quantity (ea)
1275	1264	797	2125	283			
1300	1289	813	2167	289			
1325	1315	828	2208	294			
1350	1341	844	2250	300			
1375	1366	859	2292	306			
1400	1392	875	2333	311			
1425	1417	891	2375	317			
1450	1443	906	2417	322			
1475	1469	922	2458	328			
1500	1494	938	2500	333			
1525	1520	953	2542	339			
1550	1546	969	2583	344			
1575	1571	984	2625	350			
1600	1597	1000	2667	356			
1625	1622	1016	2708	361			
1650	1648	1031	2750	367			
1675	1674	1047	2792	372			
1700	1699	1063	2833	378			
1725	1725	1078	2875	383			
1750	1751	1094	2917	389			
1775	1776	1109	2958	394			
1800	1802	1125	3000	400			
1825	1828	1141	3042	406			
1850	1854	1156	3083	411			
1875	1879	1172	3125	417			
1900	1905	1188	3167	422			
1925	1931	1203	3208	428			
1950	1956	1219	3250	433			
1975	1982	1234	3292	439			
2000	2008	1250	3333	444			
2025	2034	1266	3375	450			
2050	2059	1281	3417	456			
2075	2085	1297	3458	461			
2100	2111	1313	3500	467			
2125	2137	1328	3542	472			
2150	2162	1344	3583	478			
2175	2188	1359	3625	483			
2200	2214	1375	3667	489			
2225	2240	1391	3708	494			
2250	2265	1406	3750	500			
2275	2291	1422	3792	506			
2300	2317	1438	3833	511			
2325	2343	1453	3875	517			
2350	2368	1469	3917	522			
2375	2394	1484	3958	528			
2400	2420	1500	4000	533			
2425	2446	1516	4042	539			
2450	2471	1531	4083	544			
2475	2497	1547	4125	550			
2500	2523	1563	4167	556			

*No more than 25% of total volume can be mitigated by use of trees

VII. Stormwater Management/ BMP Facilities Operation and Maintenance Agreement

THIS AGREEMENT, made and entered into this ____ day of _____, 20____, by and between _____ hereinafter called the "Landowner" and **HAMILTON TOWNSHIP**, Adams County, Pennsylvania, hereinafter called the "Township."

WHEREAS, the Landowner is the owner of certain real property located at _____, described as _____ (*Adams County Tax Map / Parcel Identification Number*) located in Hamilton Township Adams County, Pennsylvania, as recorded by Deed in the Land Records of Adams County, Pennsylvania, Book _____ Page _____, hereinafter called the "Property";

WHEREAS, the Landowner is proceeding to build on and develop the property; and

WHEREAS, the Minor Stormwater Management Plan hereinafter called the "Plan", which is expressly made a part hereof, as approved or to be approved by the Township, provides for management of stormwater within the confines of the property through the use of Stormwater Best Management Practices (Stormwater BMPs); and

WHEREAS, the Township and the Landowner, its successors and assigns, agree that the health, safety, and welfare of the residents of the Township, require that on-site Stormwater BMPs be constructed and maintained on the Property; and

WHEREAS, the Township requires that on-site Stormwater BMPs as shown on the Plan be constructed and adequately maintained by the Landowner, its successors and assigns. Any additional requirements imposed by the Township are considered part of the Plan.

NOW, THEREFORE, in consideration of the foregoing premises, the mutual covenants contained herein, and the following terms and conditions, the parties hereto agree as follows:

1. The Landowner in accordance with the specifications identified within the Plan shall construct the onsite Stormwater BMPs.
2. The Landowner assumes full responsibility for the construction, operation, and maintenance of the proposed stormwater management facilities.
3. The Landowner, its successors and assigns, shall adequately maintain the Stormwater BMPs. This includes all pipes and channels built to convey stormwater to the facility, as well as all structures, improvements, and vegetation provided to control the quantity and quality of the stormwater. Adequate maintenance is herein defined as good working condition so that these facilities are performing their design functions.
4. The Landowner, its successors and assigns, shall inspect the Stormwater BMPs after all rainfall events exceeding one inch of precipitation in a 24-hour period.
5. The Landowner, its successors and assigns, hereby grant permission to the Township, its authorized agents and employees, to enter upon the Property without prior notification at reasonable times and upon presentation of proper identification to inspect the Stormwater BMPs whenever the Township deems necessary.
6. The Landowner acknowledges that the proposed Stormwater BMPs will be a permanent fixture of the property that cannot be altered or removed without approval by the Township.

7. In the event the Landowner, its successors and assigns, fails to maintain the Stormwater BMPs as shown on the Plan and in good working condition, the Township may enter upon the Property and take whatever action is deemed necessary to maintain said Stormwater BMPs and to charge the costs of such repairs to the Landowner, its successors and assigns. This provision shall not be construed to allow the Township to erect any structure of permanent nature on the land of the Landowner unless such structures were part of the approved Plan. It is expressly understood and agreed that the Township is under no obligation to routinely maintain or repair said facilities, and in no event shall this Agreement be construed to impose any such obligation on the Township.

8. In the event that the Township, pursuant to this Agreement, performs work of any nature, or expends any funds in performance of said work for labor, use of equipment, supplies, materials, and the like, the Landowner shall reimburse the Township within thirty (30) days of receipt of invoice for all expenses incurred. The Township has the right to file a municipal lien for unpaid costs and expenses that have not been reimbursed thirty (30) days after receipt of invoice.

9. The intent and purpose of this Agreement is to ensure the proper maintenance of the Stormwater BMPs by the Landowner. This Agreement shall not be deemed to create any additional liability of any party for damage alleged to result from or be caused by nonpoint source pollution runoff. This Agreement imposes no liability of any kind whatsoever on the Township and the Landowner agrees to hold the Township harmless from any liability in the event the Stormwater BMPs fail to operate properly. In the event that a claim is asserted against the Township, its designated representatives or employees, the Township shall promptly notify the Landowner and the Landowner shall defend, at his own expense, any suit based on the claim. If any judgment or claims against the Township shall be allowed, the Landowner shall pay all costs and expenses regarding said judgment.

10. This Agreement shall be binding to the Landowner, its administrators, executors, assigns, heirs and any other successors in interests, in perpetuity.

This Agreement shall be recorded at the Office of the Recorder of Deeds of Adams County, Pennsylvania, and shall constitute a covenant running with the Property and/or equitable servitude, and shall be binding on the Landowner, his administrators, executors, assigns, heirs, and any other successors in interests, in perpetuity.

IN WITNESS WHEREOF, the parties have executed this Agreement on the day and year first above written.

ATTEST:

ATTEST:

 Name/Title

(SEAL)

LANDOWNER:

By: _____
 Name/Title

By: _____
 Name/Title

MUNICIPALITY:

HAMILTON TOWNSHIP

By: _____
 Name/Title

STATE OF _____ : ss
COUNTY OF _____

On this, the ____ day of _____, 20____, before me, the undersigned officer, personally appeared _____, who acknowledged [himself] [herself] [themselves] to be the _____ of _____ and that [he] [she] [they] executed the within Agreement on behalf of _____ by signing [his] [her] [their] name as such _____.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My commission expires:

(SEAL)

COMMONWEALTH OF PENNSYLVANIA : ss
COUNTY OF _____




On this, the ____ day of _____, 20____, before me, the undersigned officer, personally appeared _____, who acknowledged [himself] [herself] to be the _____ of HAMILTON TOWNSHIP and that [he] [she] executed the within Agreement on behalf of HAMILTON TOWNSHIP by signing [his] [her] name as such, ____.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

My commission expires:

(SEAL)

VIII. Standard Details



DESIGN NOTE:
 CHOOSE TRENCH LENGTH TO MEET REQUIREMENT PER THE BMP SIZING CHART. TRENCHES SHALL BE INSTALLED PARALLEL TO THE EXISTING CONTOUR SUCH THAT THE TOP AND BOTTOM OF TRENCH IS INSTALLED AT A UNIFORM ELEVATION.


- NOTES:**
1. INFILTRATION TRENCHES TO BE INSTALLED IN UNDISTURBED SOIL. CONTINUOUS TRENCHES SHALL BE INSTALLED PARALLEL TO THE CONTOUR SUCH THAT THE TRENCH IS AT A UNIFORM ELEVATION THROUGHOUT.
 2. SUBGRADE BELOW THE INFILTRATION TRENCH SHOULD NOT BE COMPACTED. IF THE SUBGRADE BECOMES COMPACTED FOR ANY REASON, THE SOIL SHALL BE SCARIFIED PRIOR TO CONSTRUCTING THE BED.
 3. SEDIMENT ACCUMULATION SHALL BE MONITORED SEASONALLY.
 4. PENDING THE INSTALLATION TYPE WHEN SEDIMENT ACCUMULATES TO A DEPTH OF 18" IN THE YARD BASIN, OR AS THE TOP 4" OF RIVER STONE OR AASHITO STONE ARE CHOKED WITH DEBRIS AND SEDIMENT, IT SHALL BE REMOVED.

INFILTRATION TRENCH
 N.T.S.

**SMALL PROJECT APPROACH STANDARD DETAIL
 INFILTRATION TRENCH**


DESIGN NOTE:

1600 SQ. FT. MAX ROOF AREA PER 4" PERFORATED PIPE. IF MORE THAN 1 PIPE IS REQUIRED, THEY SHOULD BE EVENLY SPACED IN THE INFILTRATION BED. SELECT LENGTH AND WIDTH TO MEET AREA REQUIREMENT BASED ON BMP SIZING CHART.



NOTES:

1. INFILTRATION PITS TO BE INSTALLED IN UNDISTURBED SOIL.
2. SUBGRADE BELOW THE INFILTRATION PIT SHOULD NOT BE COMPACTED. IF THE SUBGRADE BECOMES COMPACTED FOR ANY REASON, THE SOIL SHALL BE SCARIFIED PRIOR TO CONSTRUCTING THE BED.
3. SEDIMENT ACCUMULATION SHALL BE MONITORED SEASONALLY.
4. WHEN SEDIMENT ACCUMULATES TO A DEPTH OF 18" IN THE YARD BASIN, IT SHALL BE REMOVED.
5. PIPING AND CLEANOUTS TO BE CENTERED WITHIN INFILTRATION BED.



TYPICAL INFILTRATION BED DETAIL
N.T.S.

SMALL PROJECT APPROACH STANDARD DETAIL
INFILTRATION BED

DESIGN NOTE:
 HOME OWNER TO CHOOSE LENGTH OF THE BERM REQUIRED BASED ON THE VOLUME REQUIRED PER THE BMP SIZING CHART. BERMS SHALL BE INSTALLED PARALLEL TO THE EXISTING CONTOUR SUCH THAT THE TOP OF BERM IS INSTALLED AT A UNIFORM ELEVATION.

CONTRACTOR'S OPTION: THE CONTRACTOR MAY CHOOSE TO STRIP THE SOD OFF OF THE FOOTPRINT AREA OF THE INFILTRATION BERM FOR REUSE AS STABILIZATION OF 3:1 EMBANKMENTS. IF EXISTING SOD IS NOT USED, THE DEVELOPER SHALL STABILIZE THE EMBANKMENTS WITH TEMPORARY MATTING, SEEDING AND MULCHING PER ADAMS COUNTY CONSERVATION DISTRICT REQUIREMENTS.

SOD OR PROVIDE TOPSOIL AND SEEDING STABILIZED WITH TEMPORARY NA GREEN S75 MATTING THROUGHOUT ENTIRE BERM.

AREA OF BERM FILL SHALL BE PLACED IN 6" LIFTS AND COMPACTED

EXISTING GROUND (SLOPE VARIES)

3 MIN.
1

3 MIN.
1

3 MIN.
1

FLows TO ENTER BERM BY OVERLAND FLOW, SWALE OR 4"-6" PVC PIPE FROM YARD DRAIN OR ROOF LEADER

THE CONTRACTOR SHALL TAKE PROPER PRECAUTIONS SO AS NOT TO COMPACT INNER BASIN SUBGRADE AREAS. HEAVY EQUIPMENT SHOULD BE KEPT OUT OF THESE AREAS.

INFILTRATION BERM DETAIL

(N.T.S.)


NOTES:

1. REMOVE TOPSOIL IN AREA OF INSTALLATION OF BERM AND STOCKPILE ABOVE. PERFORM EXCAVATION OF SUBGRADE. OVER EXCAVATING BERM BY 6" AND REPLACE WITH STOCKPILED SOIL.
2. SOIL IN THE INFILTRATION BERM BOTTOM SHOULD NOT BE COMPACTED. IF THE SUBGRADE BECOMES COMPACTED FOR ANY REASON, THE SOIL SHALL BE SCARIFIED PRIOR TO SEEDING.
3. SEDIMENT ACCUMULATION SHALL BE MONITORED SEASONALLY.
4. WHEN SEDIMENT ACCUMULATES TO A DEPTH OF 3" IN THE BERM, IT SHALL BE REMOVED.
5. BERM SOILS SHALL BE FREE OF STONES, STUMPS, ROOTS OR OTHER WOODY MATERIAL OVER 1" IN DIAMETER.
6. BERMS SHALL BE KEPT FREE FROM NOXIOUS WEEDS AND INVASIVE SPECIES
7. BERMS SHOULD BE MOWED ANNUALLY OR BIANNUALLY

PROVIDE 1' X 1' TRENCH KEY AT BERM TOE


**SIMPLIFIED APPROACH STANDARD DETAILS
 INFILTRATION BERM**

DESIGN NOTE:
TREES MUST BE PA NATIVE SPECIES, A MINIMUM OF 1" CALIPER. DEAD TREES SHALL BE REPLACED BY PROPERTY OWNER WITHIN A MINIMUM OF 12 MONTHS. NO MORE THAN 25% OF VOLUME REQUIREMENT CAN BE TAKEN FOR TREE PLANTING.




NOTES
1. SPRAY ALL TREES IN LEAF WITH ANTI-DESSICANT PRIOR TO PLANTING.
2. FLOOD SAUCER WITH WATER TWICE WITHIN 24 HOURS OF PLANTING.

DECIDUOUS TREE PLANTING DETAIL




STAKING PLAN




NOTE:
1. FLOOD SAUCER WITH WATER TWICE WITHIN 24 HOURS OF PLANTING.

EVERGREEN TREE PLANTING DETAIL
N.T.S.

SMALL PROJECT APPROACH STANDARD DETAIL
TREE PLANTING



DESIGN NOTE:
 CHOOSE LENGTH AND WIDTH TO MEET AREA REQUIREMENT PER THE BMP SIZING CHART. BERMS SHALL BE INSTALLED PARALLEL TO THE EXISTING CONTOUR SUCH THAT THE TOP OF BERM IS INSTALLED AT A UNIFORM ELEVATION.



NOTES:

1. PLANTING SOIL SHOULD BE A SANDY LOAM, LOAMY SAND, LOAM (USDA), OR A LOAM/SAND MIX. RATIO FOR RAIN GARDEN SOIL MIX SHOULD CONTAIN AN APPROXIMATE RATIO OF 50% SAND, 30% COMPOST AND 20% NATIVE SOILS
2. THE SOILS SHALL BE FREE OF STONES, STUMPS, ROOTS OR OTHER WOODY MATERIAL OVER 1" IN DIAMETER.
3. BRUSH OR SEEDS FROM NOXIOUS WEEDS SHALL NOT BE PRESENT IN THE SOILS.
4. PLACEMENT OF THE PLANTING SOIL SHOULD BE IN 9" LIFTS THAT ARE LOOSELY COMPACTED.
5. BIO-RETENTION AREA MUST BE PROTECTED FROM EROSION/SEDIMENTATION DURING CONSTRUCTION.
6. WET PLANTINGS IN RAIN GARDEN SHOULD BE NATIVE TO PA.
7. SUBGRADE IN THE RAIN GARDEN BOTTOM SHOULD NOT BE COMPACTED. IF THE SUBGRADE BECOMES COMPACTED FOR ANY REASON, IT SHALL BE SCARIFIED PRIOR TO SOIL PLACEMENT
8. DO NOT INSTALL WITHIN 10' OF A STRUCTURE

RAIN GARDEN
 N.T.S.

SIMPLIFIED APPROACH STANDARD DETAIL
RAIN GARDEN