
Sponsored by: Council Members Cook and Ragsdale

AN ORDINANCE APPROVING THE PLANS FOR THE TARA OAKS MANOR WATERMAIN EXTENSION PROJECT; DECLARING THE PROJECT TO BE NECESSARY AND APPROPRIATE; AUTHORIZING ACQUISITION OF LAND; AND AUTHORIZING CERTAIN OTHER ACTIONS.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE CITY OF O'FALLON, MISSOURI, AS FOLLOWS:

SECTION 1: The City Council finds and declares that the public water system encompassed by the plans attached hereto as Exhibit A and incorporated herein by reference depicting the proposed alignment for the TARA OAKS MANOR WATER MAIN EXTENSION PROJECT, are necessary for the public interest, in furtherance of protecting and enhancing the public health, safety and welfare, and that the construction thereof is a proper exercise of governmental authority.

SECTION 2: The City Council hereby approves the TARA OAKS MANOR WATER MAIN EXTENSION PROJECT and the plans referenced above for construction by the City of O'Fallon.

SECTION 3: The City Council also hereby authorizes the acquisition of all land, easements, and other interests necessary for the Project by purchase, donation, or through the use of eminent domain. The City Administrator, or his/her designee, is hereby authorized to execute all deeds, easements, conveyances and other documents necessary, desirable, convenient or prudent to acquire the property and interests described herein in accordance with the City's purchasing policy and the City Attorney is authorized to file such actions and pursue such legal recourse as may be necessary, prudent or useful to acquire any and all property reasonably necessary to construct the Project in accordance with state law.

SECTION 4: The City Administrator and City staff are hereby authorized and directed to perform all acts necessary, desirable, convenient or prudent to complete the project in substantial conformance with the approved plans.

SECTION 5: The City's obligation to complete the water main extension is contingent upon reimbursement of all costs, including those costs associated with the acquisition of necessary easements, by the Tara Oaks Manor Homeowners Association. The Tara Oaks Manor Homeowners Association has agreed to reimburse the City for costs associated with the Project and such agreement shall be memorialized in a Reimbursement Agreement prior to commencement of the Project. The City Administrator is hereby authorized to execute the Reimbursement Agreement on behalf of the City of O'Fallon.

SECTION 6: This ordinance shall be in full force and effect from and after its passage and approval by the Mayor.

First Reading: June 13, 2024

Second Reading: June 27, 2024

PASSED BY THE CITY COUNCIL FOR THE CITY OF O'FALLON, MISSOURI, THIS 27TH DAY OF JUNE, 2024.



Bill Hennessy

Presiding Officer

Attest:

Bess Bacher

Bess Bacher, City Clerk

APPROVED BY THE MAYOR FOR THE CITY OF O'FALLON, MISSOURI, THIS 27TH DAY OF JUNE, 2024.



Bill Hennessy

Bill Hennessy, Mayor

Attest:

Bess Bacher

Bess Bacher, City Clerk

Approved as to Form:

Stephanie Karr


Stephanie Karr, City Attorney

A SET OF CONSTRUCTION PLANS FOR TARA OAKS MANOR WATER MAIN EXTENSION


TRACTS OF LAND BEING PART OF
SECTION 12 AND PART OF SECTION 13
TOWNSHIP 47 NORTH, RANGE 2 EAST
OF THE FIFTH PRINCIPAL MERIDIAN
ST. CHARLES COUNTY, MISSOURI

Drawing Index

- 1 COVER SHEET
- 2 NOTES
- 3 PLAN & PROFILE
- 4 PLAN
- 5 DETAILS



Plan View
SCALE: 1" = 60'



Plan View
SCALE: 1" = 80'



Location Map
NOT TO SCALE

Legend

- WATER VALVE
- FIRE HYDRANT
- EX. SANITARY SEWER MANHOLE
- FLARED END SECTION
- POWER POLE
- GUY WIRE
- EX. WATER VALVE
- EX. FIRE HYDRANT
- AC UNIT
- CABLE TV BOX
- ELECTRIC BOX
- ELECTRIC TRANSFORMER
- TELEPHONE CABLE PEDESTAL
- TELEPHONE BOX
- ELECTRIC METER
- WATER METER
- BUSH
- MANHOLE
- FLARED END SECTION
- DND PIPE
- CONCRETE PIPE
- RCP REINFORCED CONCRETE PIPE
- CMR CORRUGATED METAL PIPE
- CPW CORRUGATED PLASTIC PIPE
- PVC POLY(VINYL CHLORIDE) (PLASTIC) TO BE FENCED
- TBA TO BE ABANDONED

PROJECT TITLE:
**TARA OAKS MANOR
WATER MAIN EXTENSION**

ENGINEERING
DRAWING
No. 201703031
City of O'Fallon
25 Plantation Oaks Lane
St. Paul, MO 63366
Fax 636-240-2000



UTILITY CONTACTS
Sanitary Sewers:
City of O'Fallon
100 N. Main St.
O'Fallon, MO, 63356
Contact: 636-240-2000

Water:
City of O'Fallon
100 N. Main St.
O'Fallon, MO, 63356
Contact: 636-240-2000

Storm Sewer:
City of O'Fallon
100 N. Main St.
O'Fallon, MO, 63356
636-240-2000

Electric:
Quire River Electric Co.
P.O. Box 160
Troy, MO, 63279-0160
1-800-339-3700
Ameren Missouri
200 Colahan Road
Wentzville, MO, 63385
636-639-8312

Gas:
Spire Gas
8400 Graham Road
St. Louis, MO, 63134
314-522-2297

Telephone:
CenturyLink
1151 Century Tel Dr.
Wentzville, MO, 63385
636-332-7261

Fire District:
O'Fallon Fire Protection District
111 Laura K Dr.
O'Fallon, MO, 63366
636-272-3493

Developer / Owner:
**Tara Oaks Manor HOA
25 Plantation Oaks Lane
St. Paul, MO 63366**

P+Z No. N/A
Approval Date: N/A
City No. N/A

Page No.
1 of 5

Benchmarks Project

REFERENCE BENCHMARK:
"C-149" ELEV=546.45 (NAVD88).
LOCATED 80 FEET WEST OF A TOWNSHIP ROAD CROSSING, 48 FEET NORTH OF THE CENTERLINE OF THE TRACK, 12 FEET WEST OF THE RIGHT-OF-WAY FENCE CORNER, AND 2 FEET SOUTH OF THE RIGHT-OF-WAY FENCE, A STANDARD DISK, STAMPED C 149 1935 AND SET IN THE TOP OF A CONCRETE POST PROJECTING 6 INCHES ABOVE GROUND.

Site

SITE BENCHMARK:
ELEV=524.40 SANITARY MANHOLE LOCATED IN THE LORENE DRIVE RIGHT-OF-WAY APPROXIMATELY 67 FEET FROM A FLARED END SECTION, 20 FEET EAST OF THE ASPHALT PAVEMENT AND 114 FEET FROM A POWER POLE.

**VEGETATION ESTABLISHMENT
For Urban Development Sites
APPENDIX A**

SEEDING RATES:

PERMANENT:
Grass - 150 lbs./ac.
Smooth Bromes - 100 lbs./ac.
Composites - 50 lbs./ac.

TEMPORARY:
Grass or P.P. - 150 lbs./ac. (3.75 lbs. per 1,000 sq ft)
Lime - 120 lbs./ac. (2.75 lbs. per 1,000 sq ft)

SEEDING PERIODS:
Fertilizer & Lime - March 1 to June 1
Grass - August 1 to October 1
West of Rte. - March 15 to November 1
East - March 15 to September 15

MAXIMUM WATER:
100 lbs. per 1,000 sq. ft. (4,356 lbs. per ac.)

FERTILIZER RATES:
Nitrogen - 30 lbs./ac.
Phosphoric - 30 lbs./ac.
Potassium - 30 lbs./ac.
Lime - 600 lbs./ac. ENP*

* ENP = effective nitrogen rate per State evaluation of fertilizer rates.

* City of O'Fallon Construction work hours per City Ordinance 3429 as shown in Section 500.420 of the Municipal Code of the City of O'Fallon are as follows:
October 1 through May 31
7:00 A.M. To 7:00 P.M., Monday Through Sunday
June 1 Through September 30
6:00 A.M. To 8:00 P.M., Monday Through Friday
7:00 A.M. to 8:00 P.M. Saturday and Sunday

* The area of land disturbance is 0.12 Acres.

City approval of any construction site plan does not mean that any building can be constructed on the lots without meeting the building setbacks as required by the zoning codes.
All installations and construction shall conform to the approved engineering drawings. However, if the developer chooses to make minor modifications in design and/or specifications during construction, they shall make such changes at their own risk, without any assurance that the City Engineer will accept the completed installation or construction. It shall be the responsibility of the developer to notify the City Engineer of any changes from the approved drawings. The developer may be required to correct the installed improvements so they conform to the approved engineering drawings. The developer may request a letter from the Construction Inspection Division regarding any field changes approved by the City Inspector.
Lighting values will be reviewed on site prior to the final occupancy inspection.

CITY OF O'FALLON
ENGINEERING DEPARTMENT
ACCEPTED FOR CONSTRUCTION
BY: _____ DATE: _____
PROFESSIONAL ENGINEER'S SEAL
INDICATES RESPONSIBILITY FOR DESIGN

GENERAL NOTES

- 1. Sidewalk locations shall not interfere with the sidewalk handicap ramps, or curb inlet ramps.
2. Sidewalks, curb ramps, ramps and accessible parking spaces shall be constructed in accordance with the current approved American with Disabilities Act Accessibility Guidelines (ADAAG) along with the required grades, construction materials, specifications and signage.
3. Any proposed changes to the construction shall be approved by the City Engineer.
4. All construction shall be completed prior to the construction start date.
5. All construction shall be completed prior to the construction start date.
6. All construction shall be completed prior to the construction start date.
7. All construction shall be completed prior to the construction start date.
8. All construction shall be completed prior to the construction start date.
9. All construction shall be completed prior to the construction start date.
10. All construction shall be completed prior to the construction start date.
11. All construction shall be completed prior to the construction start date.
12. All construction shall be completed prior to the construction start date.
13. All construction shall be completed prior to the construction start date.
14. All construction shall be completed prior to the construction start date.

Grading Notes

- 1. Developer must supply City Construction Inspectors with an Engineer's soil reports prior to and during site grading. The soil report will be required to contain the following information on soil test curves (Proctor reports) for projects within the City:
1.1. Maximum dry density
1.2. Optimum moisture content
1.3. Maximum and minimum allowable moisture content
1.4. Curve must be plotted to show density from a minimum of 90% Compaction and above as determined by the Modified AASHTO T-99 Compaction Test (ASTM D-1557) or from a minimum of 95% as determined by the Standard Proctor Test (ASTM D-1557, Method C) (ASTM D-698). Proctor type must be designated on document.
1.5. Curve must have at least 5 density points with moisture content and sample locations listed on document.
1.6. Specific gravity
1.7. Natural moisture content
1.8. Liquid limit
1.9. Plastic limit
Be advised that if this information is not provided to the City's Construction Inspector the City will not allow grading or construction activities to proceed on any project site.
2. All fill placed in areas other than proposed storm sewers, sanitary sewers, proposed roads, and paved areas shall be compacted from the bottom of the fill to a 90% maximum density as determined by Modified AASHTO T-99 Compaction Test or 95% of maximum density as determined by the Standard Proctor Test (ASTM D-1557). Ensure the moisture content of the soil is in excess of optimum as determined by the Standard Proctor Test. Optimum moisture content shall be determined using the same test that was used for compaction. Soil compaction curves shall be submitted to the City of O'Fallon prior to the placement of fill.
3. The surface of the fill shall be finished to a 1% slope away from the edge of the work. If at the end of a day work it would appear that there may be rain prior to the next working day, the surface shall be finished smooth. If the surface has been finished smooth for any reason, it shall be scarified before proceeding with the placement of succeeding lifts. Fill shall not be placed on frozen ground, nor shall filling operations continue when the temperature is such as to permit the layer under placement to freeze.
4. Settlement and detention basins and other structures shall be constructed during the grading operation or in accordance with the approved SWPPP.
5. When grading operations are complete or suspended for more than 14 days, permanent grass shall be established at sufficient density to provide erosion control on site. Between permanent grass seeding periods, temporary cover shall be provided according to Missouri Department of Natural Resources Protecting Water Quality - a field guide to erosion, sediment and stormwater best management practices for development sites in Missouri and Kansas. All finished grades (areas not to be disturbed by improvements) in excess of 20% slopes (5:1) shall be mulched and seeded at a rate of 100 pounds per 1000 square feet when seeded.
6. Slopes shall exceed 3 (horizontal): 1 (vertical) unless otherwise approved by the soils report and specifically located on the plans and approved by the City Engineer.
7. All low places whether on site or off site be graded to provide drainage with temporary ditches.
8. Any existing wells and/or springs which may exist on the property must be sealed in a manner acceptable to the City of O'Fallon Construction Inspection Department and following Missouri Department of Natural Resources standards and specifications.
9. [INTENTIONALLY OMITTED]
10. All trench back fills under paved areas shall be granular back fill, and compacted mechanically. All other trench back fills may be earth material (free of large clods, or stones) and compacted using either mechanical tamping or water jetting. Granular material and earth material associated with new construction outside of pavements may be jetted, tamped, or compacted to a depth of 12 inches. The jetting shall be performed with a probe that is not greater than 7.5 foot centers with the jetting probe centered over and parallel with the direction of the pipe. Trench widths greater than 10 feet will require multiple probes every 7.5 foot centers.
10.1. Depth: Trench back fills less than 8 feet deep shall be probed to a depth extending half the depth of the trench back fill, but not less than 3 feet. Trench back fill greater than 8 feet in depth shall be probed to half the depth of the trench back fill but not greater than 8 feet.
10.2. Equipment: The jetting probe shall be a metal pipe with an interior diameter of 1.5 to 2 inches.
10.3. Method: Jetting shall be performed from the lowest surface topographic point and proceed toward the highest point, and from the bottom of the trench back fill toward the surface. The flooding of each jetting probe shall be started slowly allowing slow saturation of the soil. Water is not allowed to flow away from the trench without first saturating the trench.
10.4. Surface Bridging: The contractor shall identify the locations of the surface bridging (the tendency for the upper surface to crack and drop over the trench rather than collapse and consolidate during the jetting process). The contractor shall break down the bridged areas using an appropriate method such as wheels or baskets of a basket. When surface crack is collapsed, the void shall be back filled with the same material used as trench back fill and re-jetted. Compaction of the materials within the subsurface shall be completed such that no further surface subsidence occurs.
11. Site grading
11.1. Within City right-of-way: Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed every two hundred fifty (250) feet along the centerline for each lift.
11.2. Outside of City right-of-way: Material is to be placed in eight (8) inch to twelve (12) inch loose lifts and compacted per the approved compaction requirements. One (1) compaction test will be performed at two (2) foot vertical intervals and approximately 1,000 cubic yards.
12. Access to the site from any other location other than the proposed construction entrance is strictly prohibited.

Erosion Control Notes

- 1. The Permittee shall assume complete responsibility for controlling all siltation and erosion of the project area. The Permittee shall use whatever means necessary to control erosion and siltation including, but not limited to, staked straw sides and/or siltation fabric fences (possible methods of control are detailed in the plan). Control shall commence with the clearing operations and be maintained throughout the project until completion of the work by City of O'Fallon and as required by MDOT. The Permittee's responsibilities include all design and implementation as required to prevent erosion and the depositing of silt. The City of O'Fallon and as required by MDOT may at their option direct the Permittee in his methods as deemed fit to protect property and improvements or any deposit or existing pavement shall be removed immediately. Any depositing of silt or mud in new or existing storm sewers and/or swales shall be removed after each run and affected areas cleaned to the satisfaction of the City of O'Fallon and as required by MDOT.
2. All erosion control systems are to be inspected and corrected weekly, especially within 48 hours of any rain storm resulting in one-quarter inch of rain or more. Any silt or debris leaving the site and affecting public right of way or storm water drainage facilities shall be cleaned up within 24 hours after the end of the storm.
3. Erosion control devices (silt fence, sediment basin, etc) shall be in accordance with Missouri Department of Natural Resources Protecting Water Quality - a field guide to erosion, sediment and stormwater best management practices for development sites in Missouri and Kansas.
4. This development is required to provide long term post construction BMP's such as: the impact design, source control and treatment controls that protects water quality and controls run off to maximum extent practical in compliance with Phase II (Best Storm Water Discharge Guidelines (Ord. 2032, section 402.245)
5. Graded areas shall be seeded and mulched (straw) within 14 days of stopping land disturbance activities, unless it can be shown to the City Engineer that weather conditions are not favorable, vegetative growth is to be established within 6 weeks of stopping grading work on the project. That vegetative growth established shall be protected from erosion and the standard shall be as required by EPA and DNR, (TOS coverage per square foot) Ord. 6496, Section 405.055

Water Notes

- 1. Fire hydrants shall be a maximum of 600' apart. Local fire district approval is required.
2. Coordinate with the water company on the location of water meters. For meters in the City's district, meters shall be in the right-of-way, otherwise an access easement from the right-of-way shall be provided.
3. All water main must have a minimum of 42" of cover. (City water mains)
4. Provide water valves to isolate the system.
5. All water mains shall be class 200 SDR 21 or equal with locator/tracer wires.
6. If the excavations are made in the improved portion of the right-of-way, twelve inches of granular backfill will be placed over exposed facilities and contained low strength material (CSM) or flexible fill will fill the hole with eight inches of finished surface for concrete pavement. There will be a plastic membrane placed between the rock base and the CSM to prevent the material from bleeding into the rock base. The remaining eight inches will be restored by placing a 28 day, 4,000 psi concrete mix.
7. DISINFECTING: Disinfecting shall be accomplished by placing sufficient hypochlorite granules (HTG) in each section of pipe to achieve a chlorine residual in the pipeline, upon initial filling, of 50 mg/L (PPM). HTG tablets will not be allowed. Following completion of the pipeline, it shall be slowly filled with water and a sample will be taken immediately and the chlorine residual must be 50 mg/L or greater. The solution shall be allowed to stand for 24 hours and a sample shall then be taken. The chlorine residual after 24 hours shall be 30 mg/L or greater. If the piping shows insufficient chlorine residuals in either test, the piping shall be re-maintained by the injector of hypo-chlorite solution until satisfactory results are achieved. All disinfecting shall be done by the contractor, only the testing to determine the chlorine residual will be done by the City.
8. PRESSURE TESTING: Immediately following disinfection, the piping shall be pumped to a pressure (at the HIGHEST point in the project) of 150 psi or higher where the working pressure is higher than 150 PSI as determined by the City. In such cases, the pressure shall be as specified by the City and two pressure tests shall be conducted. The first test shall be with the fire hydrant auxiliary valve open and set to 50 PSI. The second test shall be with the fire hydrant auxiliary valve closed and be to the higher pressure as directed by the City. All pumping equipment and pressure gauges shall be provided by the contractor. After achieving the test pressure, the piping shall be left closed for a series of test (2) hours. At the end of test time the pressure drop shall not exceed 2 psi. In addition, if the pressure appears, in judgment of the City's representative, to be continuing to drop, the test shall be continued for another two (2) hours and if any further drop occur, the test shall be considered a failure. If the pressure test fails, the contractor will be required to find and correct the source of the leakage. If this requires draining of the pipeline, when the leakage is corrected, the pipeline will be re-disinfected and the pressure tested again until satisfactory result are achieved. Any MDNR required notification will be performed by the contractor.
9. All taps for valves, meters, and manholes are to be constructed to within 1 inch (0.03") of finish grade. Grading around structure tops on slopes need to be accounted for.
10. BACTERIOLOGICAL TESTING: After satisfactory disinfection and pressure testing, a sample shall be taken by the contractor in the presence of a City representative and submitted to a laboratory approved by the Missouri Department of Natural Resources and the City for bacteriological analysis. After 24 hours, a second sample shall be taken in a like manner and submitted for analysis. The two samples taken on consecutive days a minimum of 24 hours apart, must be found to be "safe" by the testing laboratory, and copies of the test results must be supplied to the City. If the samples are not found to be "safe" further flushing and/or disinfection as directed by the City shall be conducted by the contractor until "safe" samples on two consecutive test days are achieved. Following successful bacteriological testing and a determination by the City that the samples are "safe", the mains may be placed into service.

PROJECT TITLE: TARA OAKS MANOR WATER MAIN EXTENSION

ENGINEERING SURVEYING 226 Plantation Oaks Lane St. Paul, MO 63366



STATE OF MISSOURI MISSOURI DEPARTMENT OF NATURAL RESOURCES




JOHN R. SWANSON CIVIL ENGINEER No. 2007032083

Table with 2 columns: DATE, CITY CHECKED. Row 1: 09/25/23, CITY CHECKED.

Table with 2 columns: DEVELOPER / OWNER, P-H-Z No., Approval Date, City No., Page No. Row 1: Tara Oaks Manor HOA, P-H-Z No. N/A, Approval Date: N/A, City No. N/A, Page No. 2 of 5

Bar Project # 22-10003 Issue Date: 09/11/2023

NOTES



PROJECT TITLE:
TARA OAKS MANOR
WATER MAIN EXTENSION

ENGINEERING
PLANNING
SURVEYING
311 North Park Blvd.
St. Paul, MN 55108
651-953-5552
FAX 651-953-1718



LIABILITY OF REGISTERED PROFESSIONAL ENGINEER:
I hereby certify that the documents submitted to be printed hereon were prepared by me or under my direct supervision and I hereby declare my responsibility for all errors, omissions, and violations of the Code of Ethics, and I am not providing any services for which I am not licensed. I am not providing any services for which I am not licensed. I am not providing any services for which I am not licensed.




JEFFREY E. SWANSON
CIVIL ENGINEER
NO. 2002030321
Box Engineering Company, Inc.
Copyright 2003
Authority No. 000552
All Rights Reserved

REVISIONS

DATE	BY	COMMENTS
09/25/23	GV	COMMENTS

Note:
Provide Groutair Backfill to all water main trenches that cross the pavement, i.e. within ten (10) feet of the edge of pavement and/or the 1:1 shear plane of the road.



WATERMAIN PROFILE
SCALES:
HORIZ. 1"=40'
VERT. 1"=10'

Note: See water site plan for horizontal bends, valves, tees, and tapping sleeve locations


- LEGEND:**
- WATER VALVE
 - FIRE HYDRANT
 - EX. SANITARY SEWER MANHOLE
 - FLARED END SECTION
 - POWER POLE
 - GUY WIRE
 - EX. WATER VALVE
 - EX. FIRE HYDRANT
 - AC UNIT
 - CABLE TV BOX
 - ELECTRIC BOX
 - ELECTRIC TRANSFORMER
 - TELEPHONE CABLE PEDESTAL
 - TELEPHONE BOX
 - ELECTRIC METER
 - WATER METER
 - TREE
 - BUSH
 - MANHOLE
 - FLARED END SECTION
 - END PIPE
 - CONCRETE PIPE
 - REINFORCED CONCRETE PIPE
 - COMP. CORRUGATED METAL PIPE
 - COMP. CORRUGATED PLASTIC PIPE
 - HIGH DENSITY POLYETHYLENE (HDPE) PIPE
 - TO BE REMOVED
 - TO BE ABANDONED

Developer / Owner:
Tara Oaks Manor HOA
26 Plantation Oaks Lane
St. Paul, MN 55108

PLAN AND PROFILE

P+Z No. N/A
Approval Date: N/A
City No. N/A

Page No.
3 of 5



PROJECT TITLE:
**TARA OAKS MANOR
 WATER MAIN EXTENSION**

DATE: 09/11/2023



PLANS AND SPECIFICATIONS are hereby accepted, and the engineer is held responsible for the design and construction of the project. The engineer is not responsible for the design and construction of any other project. The engineer is not responsible for the design and construction of any other project.



Copyright © 2023
 Box Engineering Company, Inc.
 All Rights Reserved.

REVISIONS

NO.	DATE	DESCRIPTION

CITY COMMENTS

NO.	DATE	DESCRIPTION


Developer / Owner:
 Tara Oaks Manor HOA
 28 Plantation Oaks Lane
 St. Paul, MO 63366

PLAN

P+Z No. N/A
 Approval Date: N/A
 City No. N/A

Page No.
4 of 5


NOTE: THIS DETAIL IS FROM PWSO#2



NOTES
1) SEE SPECIFICATIONS FOR ADDITIONAL DETAILS FOR BEDDING AND BACKFILL.

TYPICAL TRENCH SECTION FOR PVC PIPE
NOT TO SCALE
DETAIL "A"
PAGE 1 OF 2


NOTE: THIS DETAIL IS FROM PWSO#2




THRUST BLOCK DIMENSIONS - INCHES							
PIPE DIA.	ALL FTGS.	TEE PLUG TAPPING	90 DEGREE BEND	45 DEGREE BEND	22-1/2 BEND	11-1/4 BEND	
4	14	8	24	12	20	15	12
6	18	10	30	15	24	18	12
8	22	12	36	20	30	24	15
10	26	14	42	24	36	28	18
12	30	16	48	28	42	32	20

NOTE
FOR FITTINGS LARGER THAN 12\"/>

HORIZONTAL THRUST BLOCKING
DETAIL "C"



CROSS BLOCK DETAIL
NOT TO SCALE



TYPICAL WATER AND SEWER SEPARATION
NOT TO SCALE

CITY OF ST. PAUL ENGINEERING DEPARTMENT ST. PAUL, MINN.
WATER AND SEWER SEPARATION DETAIL

PROJECT TITLE:
TARA OAKS MANOR
WATER MAIN EXTENSION

ENGINEERING SUBMITTED:
Tara Oaks Manor HOA
26 Plantation Oaks Lane
St. Paul, MN 55108
651-835-5555
FAX 651-835-1718

DATE: 09/11/2023


REVISIONS:

NO.	DATE	DESCRIPTION


The Installation of PVC Pipe shall follow the Uni-Bell PVC Pipe Association Handbook of PVC Design and Construction.

NOTE: THIS DETAIL IS FROM PWSO#2

Buffalo box is an acceptable product to use. Tyler 562-S and 564-S are acceptable products.




GATE VALVE DETAIL
NOT TO SCALE
DETAIL "D"



NOTES
A. ALL PIPE AND FITTINGS TO BE WRAPPED IN POLYETHYLENE WRAP.
B. PROVIDE "MEGALUX" RESTRAINER FOLLOWER GLANDS FOR ALL BENDS.
C. 22 1/2 VERTICAL BENDS TO BE USED EXCEPT WHERE 45 DEGREE BENDS ARE REQUIRED.

TYPICAL CREEK OR DITCH CROSSING
NOT TO SCALE



1. FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
2. SHOULD THE FABRIC BECOME OR BECOME UNDESIRABLE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
3. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY HALF THE HEIGHT OF THE BARRIER.
4. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DESIGNED TO CONFORM WITH THE EXISTING GRADIC, PREPARED AND USED.

SILTATION FENCE DETAIL

Developer / Owner:
Tara Oaks Manor HOA
26 Plantation Oaks Lane
St. Paul, MN 55108

DETAILS

P+Z No. N/A
Approval Date: N/A
City No. N/A
Page No. 5 of 5